

AD-A109 968

METCALF AND EDDY OF NEW YORK INC NY  
NATIONAL DAM SAFETY PROGRAM. MUD LOCK C&S CANAL DAM (INVENTORY --ETC(U)  
SEP 81 G P FULTON


F/G 13/13


DACW51-81-C-0044

NL

UNCLASSIFIED

1 of 2  
A1  
A 04024





U.S. GOVERNMENT PRINTING OFFICE: 1963

AD A109968

REPORT DOCUMENTATION PAGE

1. REPORT NUMBER

2. GOVT AC. NO.

READ INSTRUCTIONS  
BEFORE COMPLETING FORM  
3. RECIPIENT'S CATALOG NUMBER

4. TITLE (and Subtitle)

Phase I Inspection Report  
Mud Lock C&S Canal Dam  
Oswego River Basin, Cayuga County, NY  
Inventory No 416

5. TYPE OF REPORT & PERIOD COVERED  
Phase I Inspection Report  
National Dam Safety Program

6. PERFORMING ORG. REPORT NUMBER

8. CONTRACT OR GRANT NUMBER

DACW51-81-C-0044

7. AUTHOR(s)

GEORGE P. FULTON

LEVEL II

9. PERFORMING ORGANIZATION NAME AND ADDRESS

Metcalf and Eddy of New York, Inc.  
60 East 42nd Street  
New York, New York 10017

10. PROGRAM ELEMENT, PROJECT, TASK  
AREA & WORK UNIT NUMBERS

12. REPORT DATE

14 September 1981

13. NUMBER OF PAGES

11. CONTROLLING OFFICE NAME AND ADDRESS

Department of the Army  
26 Federal Plaza New York District, CofE  
New York, New York 10287

14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)

Department of the Army  
26 Federal Plaza New York District, CofE  
New York, NY 10287

15. SECURITY CLASS. (of this report)

UNCLASSIFIED

15a. DECLASSIFICATION/DOWNGRADING  
SCHEDULE

15. DISTRIBUTION STATEMENT (of this Report)

Approved for public release; Distribution Unlimited.

17. DISTRIBUTION STATEMENT (of the abstract entered in this report)

18. SUPPLEMENTARY NOTES

19. KEY WORDS (Continue on reverse side if necessary and identify by block number)

Dam Safety  
National Dam Safety Program  
Visual Inspection  
Hydrology, Structural Stability

Mud Lock C&S Canal Dam  
Oswego River Basin  
Cayuga County

20. ABSTRACT (Continue on reverse side if necessary and identify by block number)

This report provides information and analysis on the physical condition of the dam as of the report date. Information and analysis are based on visual inspection of the dam by the performing organization.

Examination of available data and visual inspection of the dam  
life or property. However, several items noted which should be  
evaluated and remedied.

4-77

The hydraulic/hydrologic analysis performed indicates that the spillway has sufficient capacity to discharge the peak outflow from one-half the Probable Maximum Flood (PMF), but not from the full PMF. However, overtopping is not likely to result in failure of the dam. In any case, spillway discharges occurring during large storm events will cause flooding in downstream areas along the canal, regardless of an overtopping failure. Therefore the spillway is assessed as inadequate according to Corps of Engineers guidelines.

**OSWEGO RIVER BASIN**

**MUD LOCK C&S CANAL DAM**

**CAYUGA COUNTY, NEW YORK  
INVENTORY NO. NY 416**

**PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM**

**APPROVED FOR PUBLIC RELEASE  
DISTRIBUTION UNLIMITED**



**NEW YORK DISTRICT CORPS OF ENGINEERS**

**AUGUST 1981**

0 1 2 3 4 5 6 7 8 9


## PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, and Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.



PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM  
MUD LOCK C&S CANAL DAM  
I.D. NO. NY 416  
# 64A-369  
OSWEGO RIVER BASIN  
CAYUGA COUNTY, NEW YORK

PAGE NO.

-	ASSESSMENT	
-	OVERVIEW PHOTOGRAPH	
1	PROJECT INFORMATION	1
1.1	GENERAL	1
1.2	DESCRIPTION OF PROJECT	1
1.3	PERTINENT DATA	3
2	ENGINEERING DATA	4
2.1	GEOTECHNICAL DATA	4
2.2	DESIGN RECORDS	4
2.3	CONSTRUCTION RECORDS	4
2.4	OPERATION RECORDS	4
2.5	EVALUATION OF DATA	5
3	VISUAL INSPECTION	6
3.1	FINDINGS	6
3.2	EVALUATION OF OBSERVATIONS	7
4	OPERATION AND MAINTENANCE PROCEDURES	8
4.1	PROCEDURES	8
4.2	MAINTENANCE OF DAM	8
4.3	WARNING SYSTEM IN EFFECT	8
4.4	EVALUATION	8
5	HYDRAULIC/HYDROLOGIC	9
5.1	DRAINAGE AREA CHARACTERISTICS	9

	<u>PAGE NO.</u>
5.2 ANALYSIS CRITERIA	9
5.3 SPILLWAY CAPACITY	10
5.4 RESERVOIR CAPACITY	10
5.5 FLOODS OF RECORD	10
5.6 OVERTOPPING POTENTIAL	10
5.7 EVALUATION	10
6 STRUCTURAL STABILITY	11
6.1 EVALUATION OF STRUCTURAL STABILITY	11
7 ASSESSMENT/RECOMMENDATIONS	12
7.1 ASSESSMENT	12
7.2 RECOMMENDED MEASURES	12

#### APPENDIX

- A. PHOTOGRAPHS
- B. VISUAL INSPECTION CHECKLIST
- C. HYDROLOGIC/HYDRAULIC ENGINEERING DATA AND COMPUTATIONS
- D. REFERENCES
- E. PREVIOUS INSPECTION REPORTS AND AVAILABLE DOCUMENTS
- F. DRAWINGS



PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

Name of Dam: Mud Lock C & S Canal Dam  
State Located: New York  
County: Cayuga  
Watershed: Oswego River Basin  
Stream: Seneca River  
Date of Inspection: July 7, 1981

Assessment

Examination of available documents and a visual inspection of this dam did not reveal any conditions which constitute an immediate hazard to human life or property. However, several deficiencies were noted which should be evaluated and remedied.


The hydraulic/hydrologic analysis performed indicates that the spillway has sufficient capacity to discharge the peak outflow from one-half the Probable Maximum Flood (PMF), but not from the full PMF. However, overtopping is not likely to result in failure of the dam. In any case, spillway discharges occurring during large storm events will cause flooding in downstream areas along the canal, regardless of an overtopping failure. Therefore the spillway is assessed as inadequate according to Corps of Engineers guidelines.


The most serious deficiency is the deteriorated condition of the concrete on the retaining walls and on the spillway piers. Cracks, spalling and efflorescence throughout the structure indicate the need for more thorough maintenance work. Since the condition of the submerged section of the piers and spillway sill could not be evaluated, dewatering of the area, followed by a thorough inspection of both the concrete and steel work, is recommended. In lieu of dewatering the area, an underwater inspection of the steel and concrete may be conducted. The investigation should be commenced within six months of the date of notification of the Owner. Remedial measures deemed appropriate as a result of the investigation should be completed within 12 months.

Other deficiencies as outlined below should be corrected within 12 months of the date of notification of the Owner:


1. Cracks and spalling on the concrete retaining walls, piers, and counterweights should be repaired.
2. All steel work on the superstructure should be sandblasted, primed and repainted where necessary, to prevent continued rusting and pitting.
3. All accumulated debris should be removed from the vicinity of the taintor gates.

4. The end seals on the taintor gates should be replaced.
5. The area of minor erosion behind the upstream retaining wall on the right embankment should be backfilled and reseeded.
6. Trees and brush growing on the crest of the left embankment, and on the downstream toe of both embankments should be removed.
7. An emergency action plan should be developed for the notification and evacuation of downstream residents.

  
Edward M. Greco, P.E.  
Project Manager  
Metcalf & Eddy of New York, Inc.  
New York Registration No. 47463

  
George P. Fulton, P.E.  
Vice President  
Metcalf & Eddy of New York, Inc.  
New York Registration No. 22390

Approved By:

  
Col. W. M. Smith, Jr.  
New York District Engineer

Date:

14 Sep 81

**OVERVIEW**  
**MUD LOCK C&S CANAL DAM**  
**NY ID NO. 416**



PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM  
MUD LOCK C&S CANAL DAM  
OSWEGO RIVER BASIN  
CAYUGA COUNTY, NEW YORK

SECTION 1: PROJECT INFORMATION

1.1 GENERAL

a. Authority

The Phase I inspection reported herein was authorized by the Department of the Army, New York District, Corps of Engineers, to fulfill the requirements of the National Dam Inspection Act, Public Law 92-367.

b. Purpose of Inspection

This inspection was conducted to evaluate the existing conditions of the dam, to identify deficiencies and hazardous conditions, to determine if these deficiencies constitute hazards to life and property, and to recommend remedial measures where required.

1.2 DESCRIPTION OF PROJECT

a. Description of Dam

The Mud Lock Dam at Cayuga Lake is one of the many water level control structures on the New York State Barge Canal System. The Cayuga and Seneca Canal flows eastward from Seneca to Cayuga Lake. From Cayuga Lake water flows over the spillway at Mud Lock Dam into the Seneca River, and northward to the Erie Canal. Navigation Lock No. 1, which is situated east of the east abutment of the dam permits passage of barge and recreational water traffic into the lower Canal. An inspection of the lock was not included in the dam inspection program.

The dam consists of a spillway with concrete side walls and six bays of taintor gates separated by concrete piers. Earthfill embankments to the right and left of the spillway section are protected by vertical concrete retaining walls on the upstream and downstream sides. Beyond the toe of the walls the the earth embankment slopes at 4:1 (H:V).

The retaining walls tie into the abutments of the spillway structure. The walls and piers are founded on piles driven to the top of bedrock. The combined length of the spillway and embankments is approximately 500 feet. The maximum height of the dam is 20 feet at the abutments, downstream of the sill. The minimum height is 17 feet at the retaining walls.

The spillway section has a total length of 220 feet, and the effective length of the combined bays is 180 feet. The crest of the spillway is a concrete sill 39 feet wide at elevation (E1) 371.5 (Barge Canal Datum). According to available drawings, the sill is founded on wooden piles driven to varying depths, with sheet piling driven at the upstream and downstream ends of the sill. A timber crib was constructed

immediately downstream of the spillway to prevent scour in the discharge channel.

Flow over the spillway from Cayuga Lake is controlled by the taintor gates. The gates can be opened independently using rack and pinion mechanisms mounted on each pier. At the highest position, each gate creates an effective vertical opening of 15.5 feet, which is approximately three feet above the normal navigation elevation of the lake. Counterweights consisting of reinforced concrete blocks facilitates manual operation of the gates.

Access to the piers and handwheels is via a wood and steel walkway located upstream of the gates. The only access to the dam and spillway is a walkway along the top of the mitre gates at Lock No. 1.

There is no other outlet at the dam (other than the lock). The remains of an abandoned fish ladder can be seen adjacent to the left abutment of the dam, but the waterway has been blocked by dumped fill.

b. Location

The dam is located off Mud Lock Road, approximately two miles north of the Town of Cayuga, New York, and one mile south of the intersection of Route 20 and the Cayuga and Seneca Canal.

c. Size Classification

The dam is a maximum 20 feet high, but due to the large size of Cayuga Lake, has a maximum storage capacity of over 770,000 acre-feet. Therefore, the dam is in the "large" size category as defined by the "Recommended Guidelines for Safety Inspection of Dams".

d. Hazard Classification

The dam is classified as high hazard due to the presence of a number of homes downstream on the east side of the Canal.

e. Ownership

The dam is owned by the New York State Department of Transportation (DOT). Mr. William Schollenberger, of the Waterways Maintenance Division in Albany, was contacted concerning design and construction of the dam. Mr. Richard H. Aldrich of the Regional Waterways Office, Region 3, was contacted for information regarding operating procedures and maintenance of the dam. The Region 3 office is located at 333 East Washington Street, Syracuse, New York, 13404 (telephone 315/473-8194).

f. Purpose of the Dam

The dam is used primarily to regulate the water level in Cayuga Lake and the Cayuga and Seneca Canal for navigation purposes. In addition, its purpose is to, 1) provide additional lake storage to prevent flooding during periods of high runoff in the watershed, 2) maintain a stable recreation level in the lake, and 3) maintain a minimum flow in the Seneca River in response to local water quality requirements.

g. Design and Construction History

The dam was constructed around 1912 for the New York State Department of Transportation, Canal Division, who also designed the structure. According to representatives of the DOT, there have been no major alterations to the structure since it was originally constructed. Shortly after construction a leakage problem was noted beneath the sill, and a section of wood and steel sheeting was driven upstream of the spillway as a cut-off. In 1973 the concrete sill at bay no. 1 (the east end of the spillway) was also regouted through drill holes to prevent further seepage in this area.

1.3 PERTINENT DATA

- a. Drainage Area (square miles) 1,572
- b. Discharge at Dam (cfs)  
Spillway, water surface at retaining wall 34,392
- c. Elevation (Barge Canal Datum at Mud Lock, equal to Mean Sea Level + 1.32 ft.)  
Top of Dam (at retaining wall) 387.2  
Crest of spillway (sill) 371.5  
Original streambed 370 (approx)
- d. Reservoir - Surface Area (Acres)  
Top of Dam 42,240  
Crest of spillway 42,240
- e. Storage Capacity (acre-feet)\*  
Top of Dam 663,000  
Design Pool Elevation 528,000  
Crest of spillway (sill) 0
- f. Embankment  
Type: Earthfill with vertical concrete retaining walls adjacent to spillway; 4:1 (H:V) slopes on embankment beyond limits of walls, upstream and downstream  
Dam Length (ft): 500  
Crest width (ft); 85 (maximum at spoil bank area, right embankment)  
Height: varies; 20 ft. maximum
- g. Spillway  
Type: Six bays of taintor gates on concrete sill, operated by hand wheels.  
Length of weir: 220 feet (total)  
180 feet (effective length)
- h. Low-level outlets  
none
- i. Appurtenant Structures  
Navigation Lock No. 1, adjacent to right (east) abutment of dam.

## SECTION 2: ENGINEERING DATA

### 2.1 Geotechnical Data

#### a. Geology

Mud Lock Dam is located in the Finger Lakes Region, within the Ontario Lowland physiographic province of New York State. The province generally consists of a relatively low, flat-lying area which rises in elevation from Lake Ontario southeastward to the boundary with the Appalachian Uplands province. The Ontario Lowland is crossed by at least three major east-west trending escarpments formed by relatively resistant ridges of limestone and dolomite, which are in turn interbedded with less resistant shale units forming the lowland areas. Mud Lock Dam is located north of the escarpment formed by the Onondaga Limestone of Lower Devonian age. The area in the vicinity of the dam is underlain chiefly by Camillus shale of upper Silurian age.

Available publications do not indicate the presence of any faulting in the bedrock in the vicinity of the dam.

Depth to bedrock ranges from approximately 10 to 40 feet in the area of the navigation lock, based on available test borings. Overburden materials consist of gravel, sand, silt and clay that were deposited during and since the period of Pleistocene glaciation. The borings also show 4 to 6 feet of muck overlying the granular deposits.

#### b. Subsurface Investigations

Two drawings showing test borings and soil profiles along the Lock No. 1 canal were reviewed for this project.

### 2.2 DESIGN RECORDS

Some design drawings dated 1910 and 1912 were available at the Department of Transportation office in Albany. Several plans showing details on the embankments, spillway, and taintor gates were reviewed, and the more pertinent drawings are included in Appendix E.

### 2.3 CONSTRUCTION RECORDS

No construction records concerning the original construction of the dam were located.

### 2.4 OPERATION RECORDS

The dam is operated by personnel of the Department of Transportation, Waterways Division. The chief lock operator also regulates the position of the taintor gates as instructed by the DOT Region 3 office. Daily records of lake elevation and spillway discharge are kept by the operator and are available at the Regional office.

## 2.5 EVALUATION OF DATA

The data used for the preparation of this report was obtained from the New York State Department of Transportation. The available information appeared to be accurate.



### SECTION 3: VISUAL INSPECTION

#### 3.1 FINDINGS

##### a. General

Visual inspection of Mud Lock Dam was conducted on July 7, 1981. The weather was sunny with the temperature in the 80's. The water level at the time of the inspection was at El. 383.5, Barge Canal Datum, which is one-half foot below the top of the closed taintor gate.

##### b. Embankment

The grass cover on the right embankment was recently cut, which facilitated inspection of this side of the dam. The crest is relatively flat, with no apparent irregularities on the surface. Minor soil erosion due to runoff was noted behind the upstream retaining wall of the right abutment. Some vegetation is growing on the riprap slopes upstream and downstream of the retaining walls.

The left embankment is overgrown with brush, and the contact between the abutment and the abandoned fish ladder could not be distinguished. Gravel fill has been dumped into the fish ladder, which is now partially overgrown with vegetation. The only seepage noted on either the right or left embankment was through the fill in the fish ladder. Any seepage which may occur through the rest of the embankment would not be detected due to the tailwater.

The concrete side walls and the retaining walls, upstream and downstream, are in fair condition. Vertical construction and/or expansion joints have opened up at several places along the wall, particularly on the right embankment. Severe spalling is occurring in these areas, as well as along the upper edge of the upstream wall and along the entire surface of the downstream wall leading to the taintor gates. Heavy efflorescence was also noted on the walls.

##### c. Spillway

The spillway is in fair to poor condition, with the major deficiency being the deterioration of the concrete piers. Heavy spalling occurs on the tops of the piers, particularly toward the center of the spillway and at the gate bearing points. Efflorescence was noted through horizontal fractures in the sides of the piers, with minor amounts of vegetation growing in the cracks. The lower two-thirds of the piers, and the sill, could not be inspected due to the tailwater elevation. The submerged portion of the piers and sill was reportedly inspected in 1973 by towing a cofferdam barge upstream of the spillway and thereby cutting off the flow. Substantial leakage beneath the sill was reported in the 1973 Condition Report, which is included in Appendix E.

The rack and pinion mechanisms which operate the taintor gates appear to be in good condition, with only minor amounts of rust in some areas. Parts of the superstructure on the taintor gates have been recently painted, however, rust is visible in other areas of the beams. The steel plates on the downstream side were also rusted. The upstream side of the gates were submerged. All six counterweights on the taintor gates showed

heavy spalling on the lower corners. Five of the weights had horizontal fractures running along their entire length. In some places the fractures were as much as 3/4-inches wide.

At the time of the inspection, two of the six taintor gates were slightly open to permit a minimum flow of 200 cfs into the Seneca River. Heavy leakage was occurring around the end seals of three of the gates.

A significant accumulation of tree limbs and debris was noted on the upstream side of two of the gates. In addition, debris including several large tree trunks were caught in the lower part of the superstructure on the downstream side of the gates. Some of the debris appears to have been there long enough to sustain the growth of minor amounts of vegetation among the steel work.

d. Downstream Channel

The channel downstream of the spillway is wide and generally free from debris and overhanging trees. Part of the timber cribbing placed to prevent scour at the toe of the spillway was visible below the water surface, and appeared to be intact.

e. Reservoir Area

Cayuga Lake is approximately 35 miles long. However, due to the presence of a railroad causeway upstream of the dam, the fetch is only slightly more than one mile. There were no visible signs of instability or sedimentation problems on the perimeter within this immediate area, which consisted chiefly of low-lying vegetated marsh and woodland.

3.2 EVALUATION OF OBSERVATIONS

Visual inspection of this dam revealed the following deficiencies:

1. Heavy spalling, cracking, and efflorescence of the concrete on both the retaining walls on the embankment and the side walls, piers and counterweights on the spillway.
2. Rusted steel work on the taintor gates.
3. Heavy accumulation of debris both upstream of the gates, and lodged within the superstructure downstream of the plates.
4. Leakage around the side and bottom seals of the taintor gates.
5. Minor erosion of the soil on the earth embankment, behind the upstream retaining wall.
6. Minor growth of vegetation on the slopes beyond the retaining walls.

The reported periodic leakage under the sill could not be examined or evaluated.

## SECTION 4: OPERATION AND MAINTENANCE PROCEDURES

### 4.1 PROCEDURES

Cayuga Lake is used for recreation and is part of the New York Barge Canal System controlled by the Department of Transportation. The flow of water out of the Lake and into the Seneca River is controlled by the taintor gates. The Region 3 office of the DOT gives daily instructions to the chief lock operator for operating the gates. A minimum flow of 200 cfs is maintained in the Seneca River at all times. Maximum elevation of the Lake for navigation purposes is 384.0, Barge Canal Datum at Mud Lock. Lake level is maintained within a range of 5 feet throughout the year, with the minimum level occurring during periods of high runoff in December, January and February. The purpose is to provide additional storage and thereby avoid flooding problems during the spring thaw.

### 4.2 MAINTENANCE OF DAM

The dam is maintained by the Department of Transportation. Grass mowing and other routine maintenance is performed by the lock operator and his staff as required. Biannual maintenance inspections are reportedly made by the regional maintenance crew. In addition, technical inspections of the structure have been made every two years since 1973 by DOT personnel. Copies of these inspection reports are included in Appendix E.

### 4.3 WARNING SYSTEM IF EFFECT

There is no warning system for notification and evacuation of downstream residents.

### 4.4 EVALUATION

The operation procedures on this structure are satisfactory. However, increased maintenance efforts are required to correct the deficiencies noted in Section 3.2.

## SECTION 5: HYDRAULIC/HYDROLOGIC

### 5.1 DRAINAGE AREA CHARACTERISTICS

The drainage area to Mud Lock Dam is 1572 square miles (1,006,000 acres) as indicated on the map entitled "Oswego River Watershed" (Appendix F). The topography in the watershed changes from relatively flat and low-lying land in the northern part, to hilly terrain deeply incised by innumerable tributary streams in the southern portion. Elevations in the watershed range from 500 feet above mean sea level in the north, to over 1900 feet in the south.

This extensive watershed is generally comprised of rural, wooded and agricultural land. Areas of major development include the cities and towns of Geneva, Seneca Falls, and Ithaca.

The largest tributary into Cayuga Lake is Fall Creek, which flows westerly through Ithaca. In addition, Keuka and Seneca Lakes are hydraulically connected to Cayuga Lake by the Barge Canal System at the north end of the lake.

### 5.2 ANALYSIS CRITERIA

The large size of the watershed had to be considered in conducting the hydraulic analysis. For this reason the Probable Maximum Precipitation (PMP) was applied to three subareas of the watershed as follows: 1) rainfall directly on the lake surface, 2) runoff from the shorter tributary streams directly connected to the lake, and 3) runoff from the larger streams in the watershed, such as Fall Creek and the Cayuga-Seneca Canal. The three hydrographs were combined at the dam, and the total inflow was routed through Cayuga Lake in order to determine the peak discharge.

The hydraulic analysis assumes that for Keuka and Seneca Lakes the storage capacity in relation to watershed area is similar to that in Cayuga Lake. Therefore, the peak flow through the Cayuga-Seneca Canal into Cayuga Lake is insignificant when compared to the direct runoff into the lake. The results of the hydraulic analysis show that for runoff into Cayuga Lake an initial peak flow is a result of the rainfall directly on the lake. A second, higher peak occurs later when the runoff from the minor tributaries and remainder of the watershed reaches the dam.

The analysis of the spillway capacity of the dam and storage of the reservoir was performed using the Corp of Engineers HEC-1 computer model. The unit hydrograph was defined by the Snyder Synthetic Unit Hydrograph method, and the Modified Puls routing procedure was incorporated. The Probable Maximum Precipitation (PMP) was 19.0 inches (24 hrs., 200 sq. miles) from Hydrometeorological Report #33, in accordance with recommended guidelines of the Corps of Engineers. The floods selected for analysis were 50 and 100 percent of the Probable Maximum Flood (PMF) flows. The PMF inflow of 5,360 cfs was routed through the reservoir and the peak outflow was determined to be 67,760 cfs. The one-half PMF inflow and routed outflow were 163,180 cfs and 30,850 cfs, respectively.

### 5.3 SPILLWAY CAPACITY

The spillway consists of a concrete sill with six bays of taintor gates separated by concrete piers. The effective length of the combined bays is 180 feet. The retaining walls on the embankment are at El 387.2, which is 15.7 feet above the elevation of the sill. With the taintor gates completely open, spillway capacity to the top of the wall is 34,392 cfs. This is assuming no tailwater effect caused by flooding streams downstream of the dam.

### 5.4 RESERVOIR CAPACITY

The normal water surface is maintained at a maximum elevation of 384 (Barge Canal Datum) for navigational purposes. Cayuga Lake has a surface area of 66 square miles, and a maximum depth of 431 feet. However, for the hydraulic analysis, only the usable storage, above the elevation of the spillway sill (371.5) was considered. The effective impounding capacity at El 384 is therefore 528,000 acre-feet. Surcharge storage capacity to the top of the retaining walls (El 387.2) adds 135,000 acre-feet, which is equivalent to a direct runoff depth of 0.1 inch over the entire watershed. The total calculated usable storage is 663,000 acre-feet.

### 5.5 FLOODS OF RECORD

The maximum known discharge at the site of the dam was 10,004 cfs on July 10, 1935. As a result of Hurricane Agnes in 1972, the water level in the lake reached El 387.5, with a discharge rate of 9422 cfs flowing through the spillway. The positions of the taintor gates during this flood period are unknown.

### 5.6 OVERTOPPING POTENTIAL

The analyses indicated that with the taintor gates open, the spillway has sufficient capacity to discharge the flow from a one-half PMF storm event, but not from the full PMF. The computed depth of overtopping for the full PMF storm is 3.9 feet over the retaining wall. All storm events exceeding 60 percent of the PMF will result in the dam being overtopped.

### 5.7 EVALUATION

The hydrologic/hydraulic analysis indicated that the spillway does not have sufficient capacity to discharge the peak outflow from the full PMF. During the peak flow, the earth embankments of the dam will be overtopped. Due to the presence of the concrete retaining walls on the embankments, failure of the dam as a result of overtopping is unlikely to occur. However, during large storm events, increased spillway discharge and overtopping will result in flooding along the downstream canal regardless of an overtopping failure. Therefore, the spillway is assessed as inadequate.

## SECTION 6: STRUCTURAL STABILITY

### 6.1 EVALUATION OF STRUCTURAL STABILITY

#### a. Visual Observations

Visual inspection of the left (west) embankment and portions of the upstream slope of the right embankment was hindered by brush and trees growing in these areas. The crest of the right embankment was grass-covered and well maintained.

No areas of instability or active seepage were noted on the right embankment. Any seepage which may occur beneath the spillway could not be detected due to the tailwater. The crest of the left embankment was irregular, and covered with brush. The only seepage visible in this area was occurring through the fill that has been dumped into the abandoned fish ladder.

#### b. Design and Construction Data

Design drawings dated 1910 and 1912 are available from the DOT office in Albany. Pertinent drawings have been included in Appendix E. No other design data, specifications, or computations, and no construction records, were available.

#### c. Seismic Stability

The structure is located in seismic zone 2. No seismic stability analysis was performed.

## SECTION 7: ASSESSMENT/RECOMMENDATIONS

### 7.1 ASSESSMENT

#### a. Safety

The Phase I inspection of Mud Lock Dam revealed the following conditions:

1. Deterioration of the concrete on the side walls, piers and retaining walls of the spillway and embankments.
2. Rusting of the steel superstructure on the spillway.
3. Heavy accumulation of debris both upstream of the taintor gates, and within the superstructure.
4. Minor growth of vegetation of the crest of the left embankment, and at the downstream toe of both embankments.

The spillway capacity is inadequate for the peak outflow from the Probable Maximum Flood (full PMF). However, overtopping of the embankments is not likely to result in failure of the dam. In any case, spillway discharge during the peak flood will cause flooding in downstream areas regardless of an overtopping failure. Therefore, the spillway is assessed as inadequate, but not seriously inadequate.

#### b. Adequacy of Information

The plans which were available for the preparation of this report were fairly complete and appeared to be accurate. However, no detailed post-construction information was available for the inspection. In addition, information of the design of the embankments and the nature of the fill was not available.

#### c. Need for Additional Investigations

It is recommended that a thorough examination be made of the submerged portions of the spillway to determine the condition of the concrete, particularly at the base of the piers, and the condition of the skin plates on the gates, and to evaluate any possible seepage which may still be occurring beneath the sill. The downstream areas of the embankment should be inspected after they are cleared of brush and trees.

#### d. Urgency

The investigation of the dewatered spillway section and embankment areas should be undertaken within six months of the date of notification of the Owner. Remedial measures deemed appropriate as a result of the investigation should be complete within 12 months.

Other deficiencies as outlined below should be corrected within 12 months of the date of notification of the Owner.

### 7.2 RECOMMENDED MEASURES

- a. Cracks and spalling on the visible portions of the concrete retaining walls, piers, and counterweights should also be repaired.
- b. All steel work on the superstructure should be sandblasted, primed and repainted where necessary, to prevent continued rusting and pitting.

- c. All accumulated debris should be removed from the vicinity of the taintor gates.
- d. The end seals on the taintor gates should be replaced.
- e. The area of minor erosion behind the upstream retaining wall on the right abutment should be backfilled and reseeded.
- f. Trees and brush growing on the crest of the left embankment, and on the downstream toe of both embankments should be removed.
- g. An emergency action plan should be developed for the notification and evacuation of downstream residents.



APPENDIX A

PHOTOGRAPHS




UPSTREAM VIEW OF DAM




ACCUMULATED DEBRIS AT GATE NO. 3




**UPSTREAM RETAINING WALL AND RIGHT ABUTMENT**




**DOWNSTREAM RETAINING WALL AT RIGHT ABUTMENT**




**RACK AND PINION GATE MECHANISM**




**TAINTOR GATE (OPENED APPROXIMATELY 3 INCHES)**




**UPSTREAM RETAINING WALL AND LEFT ABUTMENT**



**DOWNSTREAM RETAINING WALL AT LEFT ABUTMENT AND  
ABANDONED FISH LADDER**



RUST ON COLUMNS AND BEAMS



SPALLING ON CONCRETE PIER

APPENDIX B

VISUAL INSPECTION CHECKLIST

VISUAL INSPECTION CHECKLIST1) Basic Data

## a. General

Name of Dam Mud Lock C+S Canal Dam  
Fed. I.D. # NY 416 DEC Dam No. 64A-367  
River Basin Oswego  
Location: Town Cayuga County Cayuga  
Stream Name Seneca River  
Tributary of Oswego River  
Latitude (N) 42° 56.3' Longitude (W) 76° 43.2'  
Type of Dam tainter-gate spillway with earth abutments and concrete retaining walls  
Hazard Category C - High  
Date(s) of Inspection July 7, 1981  
Weather Conditions sunny, 80°  
Reservoir Level at Time of Inspection 383.5 Barge Canal Datum  
b. Inspection Personnel Metcalf + Eddy: Susan Pierce, Reginald Barron,  
Carol Sweet, William Checchi; NY DOT: Richard Aldrich  
c. Persons Contacted (Including Address & Phone No.)  
Richard H. Aldrich, Regional Waterways Office, Region 3, 333 East  
Washington Street, Syracuse, N.Y., 13202 (315/473-8194)  
William Schollenberger, New York State DOT, 1220 Washington Ave,  
State Campus, Albany, New York 12232  
d. History:  
Date Constructed 1912 Date(s) Reconstructed -  
Designer New York State Canal Department  
Constructed By unknown  
Owner New York State Department of Transportation



2) Embankment

## a. Characteristics

- (1) Embankment Material soil at both abutments ; concrete  
retaining walls filled with earth
- (2) Cutoff Type wood and steel sheeting driven upstream of  
spillway sill - see drawings
- (3) Impervious Core -
- (4) Internal Drainage System none
- (5) Miscellaneous -

## b. Crest

- (1) Vertical Alignment good
- (2) Horizontal Alignment good
- (3) Surface Cracks on retaining walls: joints opened up at corners,  
minor spalling on top of wall, moderate on upstream face
- (4) Miscellaneous no appearance of differential movement  
in piers; vegetation on left embankment obscures crest

## c. Upstream Slope

- (1) Slope (Estimate) (V:H) vertical retaining walls, 1:4 rockfill slope  
beyond walls
- (2) Undesirable Growth or Debris, Animal Burrows none visible; no animal burrows noted
- (3) Sloughing, Subsidence or Depressions At upstream retaining wall,  
right embankment: runoff erosion through open corner  
joint flows back into Lake Cayuga

(4) Slope Protection some broken rock (riprap) submerged  
on upstream slope, beyond retaining wall

(5) Surface Cracks or Movement at Toe none visible (submerged)

d. Downstream Slope

(1) Slope (Estimate - V:H) vertical retaining wall; 1:4 spoil bank  
beyond wall

(2) Undesirable Growth or Debris, Animal Burrows vegetation growing  
on downstream riprap slope below retaining wall

(3) Sloughing, Subsidence or Depressions none visible; surface runoff  
has eroded soil along right end of retaining wall, right  
embankment

(4) Surface Cracks or Movement at Toe vertical joint has opened  
on corner at right (east) wall - severe spalling

(5) Seepage none at dam (none noted due to tailwater). Minor  
clear seepage occurring through dumped fill in abandoned  
fish ladder

(6) External Drainage System (Ditches, Trenches; Blanket) N/A

(7) Condition Around Outlet Structure N/A. see spillway section

(8) Seepage Beyond Toe none visible due to tailwater

e. Abutments - Embankment Contact

Concrete retaining walls tie into soil embankment; also  
tie into side walls of spillway structure

93-15-3(9/80)

(1) Erosion at Contact minor erosion due to surface runoff at upstream corner of right abutment

(2) Seepage Along Contact none  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

3) Drainage System

a. Description of System none visible  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

b. Condition of System \_\_\_\_\_  
\_\_\_\_\_

c. Discharge from Drainage System \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

4) Instrumentation (Monumentation/Surveys, Observation Wells, Weirs, Piezometers, Etc.) None

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

5) Reservoir

- a. Slopes low slopes, natural marsh vegetation; east side of Lake is vertical retaining wall, which is approach channel to navigation lock
- b. Sedimentation none visible
- c. Unusual Conditions Which Affect Dam Although Lake is approximately 35 miles long, fetch to dam is less than 1 mile due to RR causeway upstream in Lake

6) Area Downstream of Dam

- a. Downstream Hazard (No. of Homes, Highways, etc.) approximately 30 homes along C+S Canal, wildlife Refuge, Rte 20, agricultural land
- b. Seepage, Unusual Growth none visible (tailwater)
- c. Evidence of Movement Beyond Toe of Dam none
- d. Condition of Downstream Channel good - wide channel, few overhanging trees. Periodic dredging (maximum 10-yr. interval) done at confluence of discharge channel with C+S canal, approx. 3500' downstream

7) Spillway(s) (Including Discharge Conveyance Channel)

Concrete spillway section: 6 tainter gates between concrete piers

- a. General gates hand operated by rack and pinion equipment; concrete counterweights
- b. Condition of Service Spillway Fair condition - note degree of spalling of concrete, and condition of steel framework for tainter gates  
Condition of concrete sill and downstream channel could not be inspected. Piers and sill reportedly on piles, not bedrock. (see drawings)

c. Condition of Auxiliary Spillway No auxiliary spillway

---

---

---

---

d. Condition of Discharge Conveyance Channel see 7.b.

---

---

---

---

8) Reservoir Drain/Outlet Not Applicable

Type: Pipe \_\_\_\_\_ Conduit \_\_\_\_\_ Other \_\_\_\_\_

Material: Concrete \_\_\_\_\_ Metal \_\_\_\_\_ Other \_\_\_\_\_

Size: \_\_\_\_\_ Length \_\_\_\_\_

Invert Elevations: Entrance \_\_\_\_\_ Exit \_\_\_\_\_

Physical Condition (Describe): \_\_\_\_\_ Unobservable \_\_\_\_\_

Material: \_\_\_\_\_

Joints: \_\_\_\_\_ Alignment \_\_\_\_\_

Structural Integrity: \_\_\_\_\_

Hydraulic Capability: \_\_\_\_\_

Means of Control: Gate \_\_\_\_\_ Valve \_\_\_\_\_ Uncontrolled \_\_\_\_\_

Operation: Operable \_\_\_\_\_ Inoperable \_\_\_\_\_ Other \_\_\_\_\_

Present Condition (Describe): \_\_\_\_\_

\_\_\_\_\_

9) Structural

- a. Concrete Surfaces Moderate to severe spalling on concrete piers, both upstream and downstream, particularly on edges and corners. Heavy efflorescence on pier walls within each bay.
- b. Structural Cracking Minor cracking, generally horizontal along pier walls. Horizontal cracks also noted on counterweights, which are also spalled at lower corners.
- c. Movement - Horizontal & Vertical Alignment (Settlement) none noted
- d. Junctions with Abutments or Embankments junctions appear to be sound
- e. Drains - Foundation, Joint, Face none
- f. Water Passages, Conduits, Sluices abandoned fish ladder at left abutment, partially backfilled. Some clear seepage noted through fill
- g. Seepage or Leakage leakage visible around end seals of tainter gates. seepage beneath sill has been reported in old inspection records since completion of construction

- h. Joints - Construction, etc. construction joints on corners of retaining walls have opened
- i. Foundation submerged - see drawings
- j. Abutments no visible reinforcing in concrete.
- k. Control Gates superstructure in good condition except for minor rust and pitting. Some debris accumulating in framework.
- l. Approach & Outlet Channels upstream channel filled with debris at gates; below gates downstream channel fairly clear
- m. Energy Dissipators (Plunge Pool, etc.) none apparent. Timber cribbing filled with stone installed downstream of spillway to prevent scour in this area of channel
- n. Intake Structures none
- o. Stability good
- p. Miscellaneous -

10) Appurtenant Structures (Power House, Lock, Gatehouse, Other)

- a. Description and Condition Navigation Lock No. 1 adjacent  
to right (east) abutment of dam. Chief lock operator  
maintains and operates locks and tainter gates as  
required. No gate house or power house as part of  
dam appurtenances
- \_\_\_\_\_
- \_\_\_\_\_
- \_\_\_\_\_
- \_\_\_\_\_
- \_\_\_\_\_
- \_\_\_\_\_
- \_\_\_\_\_
- \_\_\_\_\_

11) Operation Procedures (Lake Level Regulation):

Lake level is maintained for navigational purposes.

Maximum desirable lake level is 384.0, Barge Canal Datum  
at Mud Lock\*. Minimum flow in Seneca River is maintained  
at 200 cfs. Gates operated as needed to maintain these  
conditions. Lake level lowered during late winter to provide  
additional storage in the event of heavy runoff.

\* Barge Canal Datum = Mean Sea Level plus 1.32 feet



APPENDIX C

HYDROLOGIC/HYDRAULIC ENGINEERING  
DATA AND COMPUTATIONS

CHECK LIST FOR DAMS  
HYDROLOGIC AND HYDRAULIC  
ENGINEERING DATA

1

AREA-CAPACITY DATA:

	<u>Elevation</u> (ft.)	<u>Surface Area</u> (acres)	<u>Storage Capacity</u> (acre-ft.)
1) Top of Dam	<u>389.8</u>	<u>42,240</u>	<u>663,168</u>
2) Design High Water (Max. Design Pool)	<u>384</u>	<u>42,240</u>	<u>528,000</u>
3) Auxiliary Spillway Crest	<u>-</u>	<u>-</u>	<u>-</u>
4) Pool Level with Flashboards	<u>-</u>	<u>-</u>	<u>-</u>
5) Service Spillway Crest	<u>371.5</u>	<u>42,240</u>	<u>0 (usable storage)</u>

DISCHARGES

	<u>Volume</u> (cfs)
1) Average Daily	<u>200 cfs</u>
2) Spillway @ Maximum High Water	<u>34392</u>
3) Spillway @ Design High Water	<u>24500</u>
4) Spillway @ Auxiliary Spillway Crest Elevation	<u>-</u>
5) Low Level Outlet	<u>-</u>
6) Total (of all facilities) @ Maximum High Water	<u>34392</u>
7) Maximum Known Flood	<u>10,004 cfs</u> , July 10, 1935
8) At Time of Inspection	<u>196 cfs</u>

CREST:

ELEVATION: 389.8 at side wall  
387.2 at earth embankmentType: earth-fill, with concrete retaining wallsWidth: 85 max. (at spoil bank) Length: 500 feet (including spillway)Spillover -Location -

SPILLWAY:

SERVICE

AUXILIARY

Elevation 371.5 (sill) 384 (top of closed gates) No auxiliary spillwayType concrete - tainter gates -Width 180 feet (effective width) -

Type of Control

no Uncontrolled -

Controlled:

Type tainter gates -  
(Flashboards; gate)Number six -Size/Length 30 feet -Invert Material -Anticipated Length of operating service permanent -Chute Length - -Height Between Spillway Crest & Approach Channel Invert (Weir Flow) approx 2' -

## HYDROMETEROLOGICAL GAGES:

Type : Continuous recording precipitation gage - Records sent to National  
Climatological Center

Location: Lock #1 at Cayuga Outlet

Records: available at Syracuse - Region 3 office

Date -                     

Max. Reading -                     

## FLOOD WATER CONTROL SYSTEM:

Warning System: no formal warning system. Report rainfall events  
greater than 1" to National Weather Service for flash flood  
warnings

Method of Controlled Releases (mechanisms):

rack and pinion mechanisms (six) - hand operated,  
one per tainter gate.

DRAINAGE AREA: 1572 square miles

DRAINAGE BASIN RUNOFF CHARACTERISTICS:

Land Use - Type: rural / agricultural

Terrain - Relief: very steep, particularly in southern half of watershed

Surface - Soil: glacial deposits

Runoff Potential (existing or planned extensive alterations to existing  
(surface or subsurface conditions)

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Potential Sedimentation problem areas (natural or man-made; present or future)

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Potential Backwater problem areas for levels at maximum storage capacity  
including surcharge storage:

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Dikes - Floodwalls (overflow & non-overflow ) - Low reaches along the  
Reservoir perimeter:

Location: Montezuma Marsh - NW of dam

Elevation: approx. 385 (MSL)

Reservoir: Cayuga Lake

Length @ Maximum Pool 35 (Miles)

Length of Shoreline (@ Spillway Crest) 74 (Miles)

NONREPRODUCIBLE GRID FORM 148

METCALF & EDDY, ENGINEERS

DRAINAGE AREA: The total drainage area of Cayuga Lake is 1572 sq mi, 749 sq mi of which drain into Seneca Lake. The remaining 823 sq mi drain into Cayuga Lake and therefore will be used to calculate the runoff.

Furthermore, the drainage area will be subdivided into 3 sections

- ① area associated with principle stream
- ② " " " shorter streams
- ③ the Lake surface

Lake area = 66 sq mi

Area of principle stream drainage = 40% land area

$$(.40)(823-66) \text{ sq mi} = 302.8 \text{ sq mi}$$

Area of shorter streams

$$823-66-302.8 = 454.2 \text{ sq mi}$$

### WATERSHED PARAMETERS

- ① Lake surface To calculate the runoff, Snyder's method uses the equation

$$q_p = \frac{C_p 640}{t_p}$$

Because rainfall onto the water surface equals the total surface runoff and one inch of runoff per hour from one square mile equals 640 cfs., then  $C_p$  and  $t_p$  must both be unity to eliminate them as factors in the conversion of rainfall to runoff

(Reference: "Synthetic Unit-Graphs" by Franklin F. Snyder Transactions, American Geophysical Union, Hydrology, 1938)

- ② Principal stream  
 Snyder Unit Hydrograph  
 Lag time

$$t_p = 4 (LL_c)^{0.3}$$

$$= 2.0 (34.14)^{0.3} = 12.71 \text{ hrs.}$$

Unit rainfall duration

$$t_r = t_p / 5.5$$







### SPILLWAY

Tainter Gate Structure - 6 gates @ 30 ft clearance

Assume that at the start of the storm, the tainter gates are fully open. Flow over spillway is that for a broad crested weir.

(Ref: Davis, "Handbook of Applied Hydraulics" - pg 1225)

$$Q = 0.9 CLH^{1.5}$$

$$= 0.9 [3.09 (6)(30) H^{1.5}] = 500 H^{1.5}$$

Note: The top of the retaining wall is at EL 387.2. Though the top of the dam is given as 389.8, the dam will start to overtop at EL 387.2

### DISCHARGE - DOWNSTREAM CHANNEL

The downstream channel is the Cayuga and Seneca Canal, which is laid on an extremely flat slope. Directly adjacent to the left side of the canal is the Montezuma Marsh, which is approximately 5 sq mi of open, flat land. When flood discharge overtops the canal, water will be attenuated in the marsh. Flow control will occur approximately 1 mi downstream, where RT 20 crosses the marsh. The roadway will control flow as a broad-crested weir, where


$$Q = 2.7 LH^{1.5}$$

11		700		250		300	
WSE	H	H	L	$Q = 2.7 LH^{1.5} + 2.7(250)H^{1.5}$			
382	2	1	1400	3780	1910	5690	
383	3	1.5	2100	10420	3510	13930	
384	4	2	2800	21380	5400	26780	

Project NV C&E PH I DAM INSP Acct. No. 7594 Page      of       
 Subject MUD LOCK DAM Comptd. By M. NOWAK Date 8/27/81  
 Detail                      Ch'd. By                      Date                     

NONREPRODUCIBLE GRID FORM 1a3

METCALF & EDDY, ENGINEERS



.....  
 FLOOD HYDROGRAPH PACKAGE (HEC-1)  
 DAM SAFETY VERSION JULY 1978  
 LAST MODIFICATION 25 SEP 78  
 .....

1	A	NEW YORK C.O.F E. PHASE 1 DAM INSPECTION	MUD LOCK DAM	FULL AND HALF PRF FLOOD ANALYSIS	0	0	0	0	0
2	A								
3	A								
4	R	100	2	0	0	0	0	0	0
5	B1	5							
6	J	1	4	1					
7	J1	0.5	0.6	0.7	1.3				
8	K	0	1						
9	K1								
10	H	1	1	AREA 1 RUNOFF DIRECT TO LAKE SURFACE	0	0	1		
11	P	0	21	66	0	0		1	
12	T			79	89	98	107		
13	W	1.0	1.3					0	1
14	X	0		1.5					
15	K	0	2						
16	K1			AREA 2 RUNOFF FROM PRINCIPAL STREAMS	0	0	1		
17	H	1	1	303	0	0			
18	P	0	21	64	73	80	89		1
19	T							1.0	0.1
20	W	12.6	0.6						
21	X	47	-0.15	1.5					
22	K	0	3					0	
23	K1			AREA 3 RUNOFF FROM SHORTER STREAMS	0	0	1		
24	H	1	1	454	0	0			
25	P	0	21	60	69	76	84		1
26	T							1.0	0.1
27	W	8.7	0.6						
28	X	1.3	-0.15	1.5					
29	K	3	DAM					0	
30	K1			COMBINE SUBAREA HYDROGRAPHS AT DAM	0	0	1		
31	K	1	DAM		0	0		0	
32	K1			ROUTE INFLOW THROUGH CATUGA LAKE	1	1			
33	Y								
34	Y1	20							
35	SS	0	486000	570760	655760	740760	825760	910760	995760
36	SE	371.5	383.0	365.0	387.3	389.0	391.0	393.0	395.0
37	SS	371.5	180	3.1	1.5				
38	SR	10	0	0					
39	SF	6	0	12	371.5	300.0	0	11.5	383.0
40	ST	371.5	373.0	375.0	377.3	380.0	383.0	384.0	
41	SW	0	920	3280	6453	12400	13930	26780	
42	SD	387.2	2.6	1.5	1000.3				
43	K	99							

PREVIEW OF SEQUENCE OF STREAM NETWORK CALCULATIONS

RUNOFF HYDROGRAPH AT	1
RUNOFF HYDROGRAPH AT	2
RUNOFF HYDROGRAPH AT	3
COMBINE 3 HYDROGRAPHS AT	DAM
ROUTE HYDROGRAPH TO	DAM
END OF NETWORK	

.....  
 FLOOD HYDROGRAPH PACKAGE (HEC-1)  
 DAN SAFETY VERSION JULY 1978  
 LAST MODIFICATION 25 SEP 78  
 .....

RUN DATE: 26 AUG 1981

NEW YORK C.O.F E. PHASE 1 DAM INSPECTION  
 MUD LOCK DAM  
 FULL AND HALF PMF FLOOD ANALYSIS

JOB SPECIFICATION									
NO	RNR	WHIN	IDAY	IHR	ININ	HETRC	IPLT	IPRT	INSTAN
100	2	0	0	0	0	0	0	0	0
			JOPER	NWT	LROPT	TRACE			
			5	0	0	0			

MULTI-PLAN ANALYSES TO BE PERFORMED  
 NPLAN= 1 NRTIO= 4 LRTIO= 1  
 NRTIOS= 0.50 0.60 0.70 1.00

.....

SUB-AREA RUNOFF COMPUTATION  
 AREA 1 RUNOFF DIRECT TO LAKE SURFACE

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	IMANE	ISTAGE	IAUTO
1	0	0	0	0	0	1	0	0

HYDROGRAPH DATA

TAREA	SNAP	TRSDA	TRSPC	RATIO	ISHOW	ISANE	LOCAL
1	66.00	0.0	66.00	0.0	0	1	0

PRECIP DATA

SPFE	PHS	R6	R12	R24	R48	R72	R96
0.0	21.00	79.00	89.00	98.00	107.00	0.0	0.0

TRSPC COMPUTED BY THE PROGRAM IS 0.857

LOSS DATA

LROPT	STRKR	DLTKR	RTIOL	ERAIN	STRKS	RTIOK	STRTL	CMSTL	ALSHZ	BTINP
0	0.0	0.0	1.00	0.0	0.0	1.00	0.0	0.0	0.0	1.00

UNIT HYDROGRAPH DATA

TP= 1.00 CP=1.00 NTA= 0

RECESSION DATA

STRTC= 0.0 QRCSN= 0.0 RTIOR= 1.50

TC INCREASED TO TNRH OF 2.00  
 CLARK DID NOT CONVERGE TO GIVEN SNYDER COEFFICIENTS  
 APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SNYDER CP AND TP ARE TC= 1.00 AND R= 0.50 INTERVALS

UNIT HYDROGRAPH 2 END-OF-PERIOD ORDINATES, LAG= 1.57 HOURS, CP= 0.50 VOL= 1.00  
 106#3. 106#3.

NO.DA

HR.NN

PERIOD

RAIN

EXCS

LOSS

END-OF-PERIOD FLOW

NO.DA

HR.NN

PERIOD

RAIN

EXCS

LOSS

END-OF-PERIOD FLOW

NO.DA

HR.NN

PERIOD

1.01	2.00	1	0.02	0.02	0.02	0.0	211.	1.05	6.00	51	0.0	0.0	0.0	0.0
1.01	4.00	2	0.02	0.02	0.02	0.0	422.	1.05	8.00	52	0.0	0.0	0.0	0.0
1.01	6.00	3	0.02	0.02	0.02	0.0	422.	1.05	10.00	53	0.0	0.0	0.0	0.0
1.01	8.00	4	0.06	0.06	0.06	0.0	797.	1.05	12.00	54	0.0	0.0	0.0	0.0
1.01	10.00	5	0.06	0.06	0.06	0.0	1172.	1.05	14.00	55	0.0	0.0	0.0	0.0
1.01	12.00	6	0.06	0.06	0.06	0.0	1172.	1.05	16.00	56	0.0	0.0	0.0	0.0
1.01	14.00	7	0.34	0.34	0.34	0.0	4198.	1.05	18.00	57	0.0	0.0	0.0	0.0
1.01	16.00	8	0.69	0.69	0.69	0.0	10975.	1.05	20.00	58	0.0	0.0	0.0	0.0
1.01	18.00	9	0.27	0.27	0.27	0.0	10281.	1.05	22.00	59	0.0	0.0	0.0	0.0
1.01	20.00	10	0.03	0.03	0.03	0.0	3234.	1.06	0.0	60	0.0	0.0	0.0	0.0
1.01	22.00	11	0.03	0.03	0.03	0.0	633.	1.06	2.00	61	0.0	0.0	0.0	0.0
1.02	0.0	12	0.03	0.03	0.03	0.0	633.	1.06	4.00	62	0.0	0.0	0.0	0.0
1.02	2.00	13	0.22	0.22	0.22	0.0	2614.	1.06	6.00	63	0.0	0.0	0.0	0.0
1.02	4.00	14	0.22	0.22	0.22	0.0	4596.	1.06	8.00	64	0.0	0.0	0.0	0.0
1.02	6.00	15	0.22	0.22	0.22	0.0	4596.	1.06	10.00	65	0.0	0.0	0.0	0.0
1.02	8.00	16	0.60	0.60	0.60	0.0	8681.	1.06	12.00	66	0.0	0.0	0.0	0.0
1.02	10.00	17	0.60	0.60	0.60	0.0	12766.	1.06	14.00	67	0.0	0.0	0.0	0.0
1.02	12.00	18	0.60	0.60	0.60	0.0	12766.	1.06	16.00	68	0.0	0.0	0.0	0.0
1.02	14.00	19	3.70	3.70	3.70	0.0	45716.	1.06	18.00	69	0.0	0.0	0.0	0.0
1.02	16.00	20	7.53	7.53	7.53	0.0	119510.	1.06	20.00	70	0.0	0.0	0.0	0.0
1.02	18.00	21	2.99	2.99	2.99	0.0	111946.	1.06	22.00	71	0.0	0.0	0.0	0.0
1.02	20.00	22	0.32	0.32	0.32	0.0	35215.	1.07	0.0	72	0.0	0.0	0.0	0.0
1.02	22.00	23	0.32	0.32	0.32	0.0	6894.	1.07	2.00	73	0.0	0.0	0.0	0.0
1.03	0.0	24	0.32	0.32	0.32	0.0	6894.	1.07	4.00	74	0.0	0.0	0.0	0.0
1.03	2.00	25	0.0	0.0	0.0	0.0	3447.	1.07	6.00	75	0.0	0.0	0.0	0.0
1.03	4.00	26	0.0	0.0	0.0	0.0	0.	1.07	8.00	76	0.0	0.0	0.0	0.0
1.03	6.00	27	0.0	0.0	0.0	0.0	0.	1.07	10.00	77	0.0	0.0	0.0	0.0
1.03	8.00	28	0.0	0.0	0.0	0.0	0.	1.07	12.00	78	0.0	0.0	0.0	0.0
1.03	10.00	29	0.0	0.0	0.0	0.0	0.	1.07	14.00	79	0.0	0.0	0.0	0.0
1.03	12.00	30	0.0	0.0	0.0	0.0	0.	1.07	16.00	80	0.0	0.0	0.0	0.0
1.03	14.00	31	0.0	0.0	0.0	0.0	0.	1.07	18.00	81	0.0	0.0	0.0	0.0
1.03	16.00	32	0.0	0.0	0.0	0.0	0.	1.07	20.00	82	0.0	0.0	0.0	0.0
1.03	18.00	33	0.0	0.0	0.0	0.0	0.	1.07	22.00	83	0.0	0.0	0.0	0.0
1.03	20.00	34	0.0	0.0	0.0	0.0	0.	1.08	0.0	84	0.0	0.0	0.0	0.0
1.03	22.00	35	0.0	0.0	0.0	0.0	0.	1.08	2.00	85	0.0	0.0	0.0	0.0
1.04	0.0	36	0.0	0.0	0.0	0.0	0.	1.08	4.00	86	0.0	0.0	0.0	0.0
1.04	2.00	37	0.0	0.0	0.0	0.0	0.	1.08	6.00	87	0.0	0.0	0.0	0.0
1.04	4.00	38	0.0	0.0	0.0	0.0	0.	1.08	8.00	88	0.0	0.0	0.0	0.0
1.04	6.00	39	0.0	0.0	0.0	0.0	0.	1.08	10.00	89	0.0	0.0	0.0	0.0
1.04	8.00	40	0.0	0.0	0.0	0.0	0.	1.08	12.00	90	0.0	0.0	0.0	0.0
1.04	10.00	41	0.0	0.0	0.0	0.0	0.	1.08	14.00	91	0.0	0.0	0.0	0.0
1.04	12.00	42	0.0	0.0	0.0	0.0	0.	1.08	16.00	92	0.0	0.0	0.0	0.0
1.04	14.00	43	0.0	0.0	0.0	0.0	0.	1.08	18.00	93	0.0	0.0	0.0	0.0
1.04	16.00	44	0.0	0.0	0.0	0.0	0.	1.08	20.00	94	0.0	0.0	0.0	0.0
1.04	18.00	45	0.0	0.0	0.0	0.0	0.	1.08	22.00	95	0.0	0.0	0.0	0.0
1.04	20.00	46	0.0	0.0	0.0	0.0	0.	1.09	0.0	96	0.0	0.0	0.0	0.0
1.04	22.00	47	0.0	0.0	0.0	0.0	0.	1.09	2.00	97	0.0	0.0	0.0	0.0
1.05	0.0	48	0.0	0.0	0.0	0.0	0.	1.09	4.00	98	0.0	0.0	0.0	0.0
1.05	2.00	49	0.0	0.0	0.0	0.0	0.	1.09	6.00	99	0.0	0.0	0.0	0.0
1.05	4.00	50	0.0	0.0	0.0	0.0	0.	1.09	8.00	100	0.0	0.0	0.0	0.0

SUN 19.25 19.25 0.0 409791.  
( 489.)( 489.)( 0.)(11608.01)

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
119510.	90641.	31051.	11380.	409688.
CFS	2567.	879.	322.	11601.
INCHES	12.78	17.51	19.25	19.25
MM	324.49	444.65	488.89	488.89

AC-FT  
THOUS CU H

44986.  
55480.

61589.  
75968.

67717.  
83528.

67717.  
83528.





CMS  
INCHES  
MM

2369.

1797.  
8.94  
227.14

615.  
12.25  
311.25

226.  
13.47  
342.22

8121.  
13.47  
342.22

AC-FT  
THOUS CU M

31452. 43112. 47402. 47402.  
38808. 53178. 58469. 58469.

# HYDROGRAPH AT STA 1 FOR PLAN 1, RTIO 4

211.	422.	797.	1172.	1172.	4198.	10975.	10281.	3234.
633.	2614.	4596.	8681.	12766.	12766.	12766.	45716.	119510.
111946.	6894.	3447.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
119510.	90641.	31051.	11380.	409688.
3384.	2567.	879.	322.	11601.
CFS				
CMS				
INCHES				
MM				
AC-FT				
THOUS CU M				

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

## SUB-AREA RUNOFF COMPUTATION

### AREA 2 RUNOFF FROM PRINCIPAL STREAMS

ISTAQ	ICOMP	ICOM	ITAPE	JPLT	JPRT	ISAGE	ISTAGE	IAUTO
2	0	0	0	0	0	1	0	0

### HYDROGRAPH DATA

INWDG	IUNG	TAREA	SNAP	TRSDA	TRSPC	RATIO	ISNOW	ISARE	LOCAL
1	1	303.00	0.0	303.00	0.0	0.0	0	1	0

### PRECIP DATA

SPFE	PMS	R6	R12	R24	R48	R72	R96
3.0	21.00	64.00	73.00	80.00	89.00	0.0	0.0

TRSPC COMPUTED BY THE PROGRAM IS 0.891

### LOSS DATA

LEOPT	STERR	DLTER	RTIOL	ERRIN	STRKS	RTIOK	STRTL	CNSTL	ALSHK	RTIMP
0	0.0	0.0	1.00	0.3	0.0	1.00	1.00	0.10	0.0	0.0

### UNIT HYDROGRAPH DATA

TP= 12.60 CP=0.60 NTA= 0

### RECESSION DATA

STRIO= 47.00 ORCSN= -0.15 RTIOR= 1.50

APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SNYDER CP AND TP ARE TC= 7.19 AND R= 6.11 INTERVALS

UNIT HYDROGRAPH 37 END-OF-PERIOD ORIGINATES, LAG= 12.51 HOURS, CP= 0.61 VOL= 1.00  
542. 1994. 3967. 6136. 8025. 9197. 8784. 7500. 6365.

5402.  
1047.  
203.

4584.  
888.  
172.

3890.  
754.  
146.

3301.  
640.  
124.

2802.  
543.  
105.

2378.  
461.  
89.

2018.  
391.  
76.

1712.  
332.

1953.  
282.

1233.  
239.

END-OF-PERIOD FLOW									
NO. DA	HR. MN	PERIOD	RAIN	EXCS	LOSS	COMP Q	HO. DA	HR. MN	PERIOD
0									
1.01	2.00	1	0.02	0.00	0.02	45.	1.05	6.00	51
1.01	4.00	2	0.02	0.00	0.02	43.	1.05	8.00	52
1.01	6.00	3	0.02	0.00	0.02	42.	1.05	10.00	53
1.01	8.00	4	0.06	0.00	0.06	40.	1.05	12.00	54
1.01	10.00	5	0.06	0.00	0.06	38.	1.05	14.00	55
1.01	12.00	6	0.06	0.00	0.06	37.	1.05	16.00	56
1.01	14.00	7	0.35	0.00	0.35	35.	1.05	18.00	57
1.01	16.00	8	0.71	0.22	0.49	156.	1.05	20.00	58
1.01	18.00	9	0.28	0.08	0.20	526.	1.05	22.00	59
1.01	20.00	10	0.03	0.00	0.03	1088.	1.06	0.00	60
1.01	22.00	11	0.03	0.00	0.03	1738.	1.06	2.00	61
1.02	0.00	12	0.03	0.00	0.03	2341.	1.06	4.00	62
1.02	2.00	13	0.17	0.00	0.17	2759.	1.06	6.00	63
1.02	4.00	14	0.17	0.00	0.17	2928.	1.06	8.00	64
1.02	6.00	15	0.17	0.00	0.17	2788.	1.06	10.00	65
1.02	8.00	16	0.56	0.36	0.20	2633.	1.06	12.00	66
1.02	10.00	17	0.56	0.36	0.20	2991.	1.06	14.00	67
1.02	12.00	18	0.56	0.36	0.20	4112.	1.06	16.00	68
1.02	14.00	19	3.11	2.91	0.20	7447.	1.06	18.00	69
1.02	16.00	20	6.34	6.14	0.20	16961.	1.06	20.00	70
1.02	18.00	21	2.51	2.31	0.20	34581.	1.06	22.00	71
1.02	20.00	22	0.26	0.06	0.20	57477.	1.07	0.00	72
1.02	22.00	23	0.26	0.06	0.20	81132.	1.07	2.00	73
1.03	0.00	24	0.26	0.06	0.20	100687.	1.07	4.00	74
1.03	2.00	25	0.00	0.00	0.00	112306.	1.07	6.00	75
1.03	4.00	26	0.00	0.00	0.00	113923.	1.07	8.00	76
1.03	6.00	27	0.00	0.00	0.00	105610.	1.07	10.00	77
1.03	8.00	28	0.00	0.00	0.00	91968.	1.07	12.00	78
1.03	10.00	29	0.00	0.00	0.00	78452.	1.07	14.00	79
1.03	12.00	30	0.00	0.00	0.00	66731.	1.07	16.00	80
1.03	14.00	31	0.00	0.00	0.00	56679.	1.07	18.00	81
1.03	16.00	32	0.00	0.00	0.00	48104.	1.07	20.00	82
1.03	18.00	33	0.00	0.00	0.00	40825.	1.07	22.00	83
1.03	20.00	34	0.00	0.00	0.00	34647.	1.08	0.00	84
1.03	22.00	35	0.00	0.00	0.00	24404.	1.08	2.00	85
1.04	0.00	36	0.00	0.00	0.00	24954.	1.08	4.00	86
1.04	2.00	37	0.00	0.00	0.00	21178.	1.08	6.00	87
1.04	4.00	38	0.00	0.00	0.00	17574.	1.08	8.00	88
1.04	6.00	39	0.00	0.00	0.00	16631.	1.08	10.00	89
1.04	8.00	40	0.00	0.00	0.00	15970.	1.08	12.00	90
1.04	10.00	41	0.00	0.00	0.00	15335.	1.08	14.00	91
1.04	12.00	42	0.00	0.00	0.00	14726.	1.08	16.00	92
1.04	14.00	43	0.00	0.00	0.00	14141.	1.08	18.00	93
1.04	16.00	44	0.00	0.00	0.00	13579.	1.08	20.00	94
1.04	18.00	45	0.00	0.00	0.00	13039.	1.08	22.00	95
1.04	20.00	46	0.00	0.00	0.00	12521.	1.09	0.00	96
1.04	22.00	47	0.00	0.00	0.00	12024.	1.09	2.00	97
1.05	0.00	48	0.00	0.00	0.00	11546.	1.09	4.00	98
1.05	2.00	49	0.00	0.00	0.00	11087.	1.09	6.00	99
1.05	4.00	50	0.00	0.00	0.00	10446.	1.09	8.00	100

SUM 16.65 12.95 3.70 1550030.  
( 423.)( 329.)( 94.)( 43892.03)

CFS 113923. PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME  
109792. 79231. 37262. 1549307.

43872.  
15.85  
402.72

1055.  
13.73  
348.68

2244.  
9.73  
247.14

3109.  
3.37  
85.62

3226.

CMS  
INCHES  
MM

AC-FT  
THOUS CU M

54443. 157152. 221724. 256084.  
67154. 193845. 273492. 315875.

HYDROGRAPH AT STA 2 FOR PLAN 1, RTIO 1

23.	22.	21.	20.	19.	18.	18.
869.	1170.	1380.	1464.	1394.	1317.	78.
17291.	28738.	40566.	50348.	56153.	56961.	2056.
28339.	24052.	20412.	17323.	14702.	12477.	45984.
7668.	7363.	7070.	6789.	6520.	6261.	8987.
5112.	4909.	4714.	4526.	4346.	4174.	5544.
3408.	3272.	3142.	3018.	2898.	2782.	3696.
2272.	2182.	2095.	2012.	1932.	1855.	2566.
1515.	1454.	1397.	1341.	1288.	1237.	1710.
1010.	970.	931.	894.	859.	824.	1188.
						760.
						730.
						1095.
						1577.
						2366.
						3549.
						5323.
						7985.
						33366.
						8480.
						544.

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME

CFS	56961.	39616.	18631.	774654.
CMS	1613.	1122.	528.	21936.
INCHES	1.69	4.86	6.86	7.93
MM	42.81	123.57	174.34	201.36
AC-FT	27221.	78576.	110862.	128042.
THOUS CU M	33577.	96922.	136746.	157938.

HYDROGRAPH AT STA 2 FOR PLAN 1, RTIO 2

27.	26.	25.	24.	23.	22.	21.	94.
1043.	1404.	1656.	1757.	1673.	1580.	1795.	2867.
20749.	34486.	48679.	60412.	67384.	68354.	63366.	55181.
34007.	28863.	24895.	20788.	17642.	14973.	12707.	10784.
9201.	8835.	8484.	8147.	7824.	7513.	7214.	6927.
6134.	5890.	5656.	5432.	5216.	5008.	4809.	4618.
4089.	3927.	3771.	3621.	3477.	3339.	3206.	3079.
2726.	2618.	2514.	2414.	2318.	2226.	2138.	2053.
1817.	1745.	1676.	1609.	1545.	1484.	1425.	1368.
1212.	1164.	1117.	1073.	1030.	989.	950.	912.
							876.
							841.
							1314.
							1893.
							2839.
							4435.
							6652.
							9978.
							47071.
							40039.
							10177.
							4468.
							653.

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME

CFS	68354.	65875.	47539.	929584.
CMS	1936.	1855.	1346.	26323.
INCHES	2.02	5.84	8.24	9.51
MM	51.37	148.28	209.21	241.63
AC-FT	32666.	94291.	133034.	153650.
THOUS CU M	40292.	116307.	164095.	189525.

HYDROGRAPH AT STA 2 FOR PLAN 1, RTIO 3

32.	30.	29.	28.	27.	26.	25.	109.
1216.	1638.	1932.	2049.	1952.	1843.	2094.	2879.
24207.	40234.	56792.	70481.	78614.	79746.	73927.	64377.
39675.	33673.	28577.	24253.	20583.	17468.	14825.	12582.
10735.	10308.	9898.	9505.	9127.	8765.	8416.	8082.
7156.	6872.	6599.	6337.	6085.	5843.	5611.	5388.
4771.	4581.	4399.	4225.	4057.	3895.	3741.	3592.
3181.	3054.	2933.	2815.	2704.	2597.	2494.	2395.
2120.	2036.	1955.	1878.	1803.	1731.	1663.	1596.
1414.	1357.	1304.	1252.	1202.	1154.	1104.	1064.
							981.
							1533.
							2208.
							3449.
							5174.
							7761.
							11641.
							54916.
							46712.
							11873.
							762.

CFS	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
	79746.	76855.	55462.	26083.	1084515.



CMS  
INCHES  
MM  
AC-FT  
THOUS CU M

2258. 2176. 1571. 739.  
2.36 6.41 9.61  
59.93 173.00 244.08  
38110. 110007. 155206.  
47008. 135691. 191445.

30710.  
11.10  
281.90  
179259.  
221113.

# HYDROGRAPH AT STA 2 FOR PLAN 1, RTIO 4

45.	43.	42.	40.	38.	37.	35.
1738.	2341.	2759.	2928.	2768.	2633.	2991.
34581.	57477.	81132.	100687.	112306.	113923.	105610.
56679.	88104.	40825.	34647.	29404.	24954.	21178.
15335.	14726.	14141.	13579.	13039.	12521.	12024.
10223.	9817.	9427.	9053.	8693.	8347.	8016.
6816.	6545.	6285.	6035.	5795.	5565.	5344.
4544.	4363.	4190.	4023.	3863.	3710.	3563.
3029.	2909.	2793.	2682.	2576.	2473.	2375.
2019.	1939.	1862.	1788.	1717.	1649.	1583.

156.  
4112.  
91968.  
17974.  
11546.  
7697.  
5131.  
3421.  
3285.  
2190.  
2103.  
1402.

PEAK  
CFS 113923. 109792. 79231. 37262.  
CFS 3226. 3109. 2244. 1055.  
INCHES 3.37 9.73 13.73 15.85  
MM 85.62 247.14 348.68 402.72  
AC-FT 54443. 157152. 221724. 256084.  
THOUS CU M 67154. 193845. 273492. 315875.

526.  
7447.  
78452.  
16631.  
11087.  
7391.  
4928.  
3285.  
2190.  
2103.  
1402.

## SUB-AREA RUNOFF COMPUTATION

### AREA 3 RUNOFF FROM SHORTER STREAMS

INTDC	IUNG	TAREA	SNAP	TRSDA	TRSPC	RATIO	ISNOW	ISARE	LOCAL
1	1	454.00	0.0	454.00	0.0	0.0	0	1	0

PRECIP DATA  
SPFE PMS R6 R12 R24 R48 R72 R96  
0.0 21.00 60.00 69.00 76.00 84.00 0.0 0.0

#### LOSS DATA

LROPT	STKR	DLTKR	RTIOL	ERAIN	STRKS	RTIOK	STRTL	CNSTL	ALSHX	RTIRP
0	0.0	0.0	1.00	0.0	0.0	1.00	1.00	0.10	0.0	0.0

UNIT HYDROGRAPH DATA  
TP= 8.70 CP=0.60 NTA= 0

#### RECESSION DATA

STRTQ= 1.30 ORCSM= -0.15 RTIOR= 1.50  
APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SNIDER CP AND TP ARE TC= 5.04 AND R= 4.32 INTERVALS

UNIT HYDROGRAPH 26 END-OF-PERIOD ORDINATES, LAG= 8.72 HOURS, CP= 0.60 VOL= 1.00  
1894. 6860. 13182. 18245. 19981. 17860. 14175. 11237. 8908. 7062.

NO. DA	HR. MN	PERIOD	RAIN	EXCS	LOSS	COMP Q	END-OF-PERIOD FLOW			HR. MN	PERIOD	RAIN	EXCS	LOSS	COMP Q
NO. DA	HR. MN	PERIOD	RAIN	EXCS	LOSS	COMP Q	NO. DA	HR. MN	PERIOD	RAIN	EXCS	LOSS	COMP Q		
1.01	2.00	1	0.02	0.00	0.02	1.	1.05	6.00	51	0.0	0.0	0.0	15799.		
1.01	4.00	2	0.02	0.00	0.02	1.	1.05	8.00	52	0.0	0.0	0.0	15172.		
1.01	6.00	3	0.02	0.00	0.02	1.	1.05	10.00	53	0.0	0.0	0.0	14569.		
1.01	8.00	4	0.06	0.00	0.06	1.	1.05	12.00	54	0.0	0.0	0.0	13990.		
1.01	10.00	5	0.06	0.00	0.06	1.	1.05	14.00	55	0.0	0.0	0.0	13434.		
1.01	12.00	6	0.06	0.00	0.06	1.	1.05	16.00	56	0.0	0.0	0.0	12900.		
1.01	14.00	7	0.31	0.00	0.31	1.	1.05	18.00	57	0.0	0.0	0.0	12388.		
1.01	16.00	8	0.63	0.12	0.51	228.	1.05	20.00	58	0.0	0.0	0.0	11895.		
1.01	18.00	9	0.25	0.05	0.20	919.	1.05	22.00	59	0.0	0.0	0.0	11423.		
1.01	20.00	10	0.03	0.00	0.03	1926.	1.06	0.0	60	0.0	0.0	0.0	10969.		
1.01	22.00	11	0.03	0.00	0.03	2850.	1.06	2.00	61	0.0	0.0	0.0	10533.		
1.02	0.0	12	0.03	0.00	0.03	3312.	1.06	4.00	62	0.0	0.0	0.0	10114.		
1.02	2.00	13	0.18	0.00	0.18	3145.	1.06	6.00	63	0.0	0.0	0.0	9713.		
1.02	4.00	14	0.18	0.00	0.18	2597.	1.06	8.00	64	0.0	0.0	0.0	9327.		
1.02	6.00	15	0.18	0.00	0.18	2060.	1.06	10.00	65	0.0	0.0	0.0	8956.		
1.02	8.00	16	0.57	0.37	0.20	2326.	1.06	12.00	66	0.0	0.0	0.0	8600.		
1.02	10.00	17	0.57	0.37	0.20	4498.	1.06	14.00	67	0.0	0.0	0.0	8258.		
1.02	12.00	18	0.57	0.37	0.20	9053.	1.06	16.00	68	0.0	0.0	0.0	7930.		
1.02	14.00	19	2.94	2.74	0.20	20019.	1.06	18.00	69	0.0	0.0	0.0	7615.		
1.02	16.00	20	6.00	5.80	0.20	49255.	1.0	20.00	70	0.0	0.0	0.0	7313.		
1.02	18.00	21	7.38	2.18	0.20	101090.	1.06	22.00	71	0.0	0.0	0.0	7022.		
1.02	20.00	22	0.26	0.06	0.20	160972.	1.07	0.0	72	0.0	0.0	0.0	6743.		
1.02	22.00	23	0.26	0.06	0.20	206010.	1.07	2.00	73	0.0	0.0	0.0	6475.		
1.03	0.0	24	0.26	0.06	0.20	218782.	1.07	4.00	74	0.0	0.0	0.0	6218.		
1.03	2.00	25	0.0	0.0	0.0	198546.	1.07	6.00	75	0.0	0.0	0.0	5971.		
1.03	4.00	26	0.0	0.0	0.0	163241.	1.07	8.00	76	0.0	0.0	0.0	5733.		
1.03	6.00	27	0.0	0.0	0.0	130427.	1.07	10.00	77	0.0	0.0	0.0	5506.		
1.03	8.00	28	0.0	0.0	0.0	103478.	1.07	12.00	78	0.0	0.0	0.0	5287.		
1.03	10.00	29	0.0	0.0	0.0	82478.	1.07	14.00	79	0.0	0.0	0.0	5077.		
1.03	12.00	30	0.0	0.0	0.0	65385.	1.07	16.00	80	0.0	0.0	0.0	4875.		
1.03	14.00	31	0.0	0.0	0.0	51833.	1.07	18.00	81	0.0	0.0	0.0	4681.		
1.03	16.00	32	0.0	0.0	0.0	41090.	1.07	20.00	82	0.0	0.0	0.0	4495.		
1.03	18.00	33	0.0	0.0	0.0	32780.	1.07	22.00	83	0.0	0.0	0.0	4317.		
1.03	20.00	34	0.0	0.0	0.0	31477.	1.08	0.0	84	0.0	0.0	0.0	4145.		
1.03	22.00	35	0.0	0.0	0.0	30227.	1.08	2.00	85	0.0	0.0	0.0	3980.		
1.04	0.0	36	0.0	0.0	0.0	29025.	1.08	4.00	86	0.0	0.0	0.0	3822.		
1.04	2.00	37	0.0	0.0	0.0	27872.	1.08	6.00	87	0.0	0.0	0.0	3670.		
1.04	4.00	38	0.0	0.0	0.0	26765.	1.08	8.00	88	0.0	0.0	0.0	3525.		
1.04	6.00	39	0.0	0.0	0.0	25701.	1.08	10.00	89	0.0	0.0	0.0	3385.		
1.04	8.00	40	0.0	0.0	0.0	24680.	1.08	12.00	90	0.0	0.0	0.0	3250.		
1.04	10.00	41	0.0	0.0	0.0	23699.	1.08	14.00	91	0.0	0.0	0.0	3121.		
1.04	12.00	42	0.0	0.0	0.0	22758.	1.08	16.00	92	0.0	0.0	0.0	2997.		
1.04	14.00	43	0.0	0.0	0.0	21853.	1.08	18.00	93	0.0	0.0	0.0	2878.		
1.04	16.00	44	0.0	0.0	0.0	20985.	1.08	20.00	94	0.0	0.0	0.0	2763.		
1.04	18.00	45	0.0	0.0	0.0	20151.	1.08	22.00	95	0.0	0.0	0.0	2654.		
1.04	20.00	46	0.0	0.0	0.0	19350.	1.09	0.0	96	0.0	0.0	0.0	2548.		
1.04	22.00	47	0.0	0.0	0.0	18581.	1.09	2.00	97	0.0	0.0	0.0	2447.		
1.05	0.0	48	0.0	0.0	0.0	17843.	1.09	4.00	98	0.0	0.0	0.0	2350.		
1.05	2.00	49	0.0	0.0	0.0	17134.	1.09	6.00	99	0.0	0.0	0.0	2256.		
1.05	4.00	50	0.0	0.0	0.0	16453.	1.09	8.00	100	0.0	0.0	0.0	2167.		
SUM 15.85 12.18 3.67 2398517.															
( 402. )( 309. )( 93. )( 67918.55 )															

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	218782.	201517.	127318.	57706.	2397433.
CMS	6195.	5736.	3605.	1634.	67888.

[illegible]

3277.	3147.	3022.	2786.	2676.	2569.	2467.	2369.	2275.
2185.	2098.	1934.	1858.	1784.	1713.	1645.	1579.	1517.

HYDROGRAPH AT STA 3 FOR PLAN 1, RTIO 4

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	248782.	201517.	127318.	57706.	2397433.
CFS	6195.	5706.	3605.	1634.	67888.
INCHES		4.13	10.43	14.19	16.37
		104.88	265.04	360.39	415.91
AC-FT		99926.	252531.	343372.	396270.
THOUS CU YD		123257.	311493.	423544.	488792.

.....

• • • • •

.....

.....

.....

# COMBINE SUBAREA HYDROGRAPHS AT DAN

ISTAQ	ICOMP	ISECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
DAM	3	0	0	0	0	1	0	0

OF 3 HYDROGRAPHS AT DAN PLAN 1 RTIO 1

129.	233.	232.	419.	606.	605.	2117.	5680.	5862.	3124.
2610.	3143.	4259.	5060.	4722.	6820.	10127.	9296.	36591.	92863.
123809.	12632.	147018.	163181.	157149.	138580.	118019.	17923.	80465.	60658.
54256.	44597.	36802.	33062.	29815.	26990.	24525.	22369.	21166.	20325.
19517.	18742.	17997.	17282.	16595.	15936.	15302.	14694.	14111.	13550.
13011.	12894.	11998.	11521.	11063.	10624.	10202.	9796.	9407.	9033.
8674.	8330.	7999.	7681.	7376.	7083.	6801.	6531.	6271.	6022.
5783.	5553.	5332.	5121.	4917.	4722.	4534.	4354.	4181.	4015.
3550.	3702.	3555.	3414.	3278.	3148.	3023.	2903.	2787.	2677.
2855.	2700.	2570.	2468.	2370.	2289.	2215.	2135.	2058.	1984.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	163181.	154377.	113110.	52108.	2178214.
CHS	4621.	4371.	3203.	1476.	61680.
INCHES		1.74	5.11	7.07	8.21

MM  
AC-FT  
THOUS CU H

44.32  
76551.  
94424.

129.89  
228351.  
276733.

179.52  
310061.  
382456.

208.45  
360035.  
444098.



SUM OF 3 HYDROGRAPHS AT		DAM PLAN 1		RTIO 2	
154.	280.	279.	503.	727.	6816.
3133.	3772.	5111.	6072.	5666.	15559.
148571.	152199.	176421.	195818.	188579.	117508.
65107.	53516.	44163.	39674.	35778.	26843.
23421.	22490.	21596.	20738.	19914.	17633.
15614.	14993.	14398.	13825.	13276.	11756.
10409.	9996.	9598.	9217.	8851.	7837.
6939.	6664.	6399.	6145.	5900.	5225.
4626.	4442.	4266.	4096.	3934.	3483.
3084.	2962.	2844.	2731.	2622.	2322.

PEAK		24-HOUR		72-HOUR		TOTAL VOLUME	
CFS	195818.	185252.	135732.	62529.	2613857.		
CMS	5545.	5245.	3444.	1771.	74016.		
INCHES		2.09	6.14	8.48	9.85		
MM		53.18	155.87	215.42	250.14		
AC-FT	91851.	269221.	372074.		432042.		
THOUS CU W	113339.	332080.	458947.		532917.		

SUM OF 3 HYDROGRAPHS AT		DAM PLAN 1		RTIO 3	
180.	327.	325.	547.	848.	7952.
3655.	4400.	5963.	7084.	6610.	18178.
173332.	177565.	205825.	228454.	220009.	165226.
75958.	62436.	51523.	46287.	41741.	34335.
27324.	26238.	25196.	24195.	23233.	21423.
18216.	17492.	16797.	16130.	15489.	14282.
12144.	11661.	11198.	10753.	10326.	9143.
8096.	7774.	7465.	7169.	6884.	6095.
5397.	5183.	4977.	4779.	4589.	4064.
3598.	3455.	3318.	3186.	3060.	2709.

PEAK		24-HOUR		72-HOUR		TOTAL VOLUME	
CFS	228454.	216128.	158354.	72951.	3049500.		
CMS	6469.	6120.	4484.	2066.	86352.		
INCHES		2.44	7.16	9.89	11.49		
MM		62.05	181.85	251.32	291.83		
AC-FT	107171.	314091.	434086.		504050.		
THOUS CU W	132193.	387426.	535438.		621737.		

SUM OF 3 HYDROGRAPHS AT		DAM PLAN 1		RTIO 4	
257.	467.	465.	838.	1212.	11359.
5221.	6286.	8519.	10120.	9443.	25932.
247618.	253665.	294036.	326363.	314299.	195846.
108512.	89194.	73604.	66124.	59630.	44739.
39034.	37483.	35994.	34564.	33190.	29389.
26023.	24989.	23996.	23042.	22127.	19593.
17349.	16659.	15997.	15362.	14751.	13602.
11566.	11106.	10665.	10241.	9834.	8708.
7710.	7404.	7110.	6827.	6554.	5805.

5140.

4936.

4740.

4552.

4371.

4197.

4030.

3870.

3716.

3569.

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME



19890.  
20215.  
30434.

19766.  
20977.  
30669.

19650.  
22068.  
30793.

19541.  
23598.  
30844.

19435.  
25168.  
30852.

19336.  
26579.  
30821.

19257.  
27781.  
30759.

19201.  
28773.  
30668.

19242.  
29520.  
30558.

19572.  
30062.  
30437.



STORAGE

482503.	479041.	475615.	472232.	468911.	462526.	459944.	457751.	455321.
452587.	449875.	447346.	445025.	442766.	439177.	438276.	439996.	449599.
				440697.				

467750. 489120. 512572. 539338. 566795. 591502. 612048. 628333. 640715. 649803.  
 656196. 660392. 662815. 664070. 664620. 664564. 663988. 662968. 661623. 660098.  
 658430. 656627. 654698. 652649. 650887. 648219. 645852. 643392. 640845. 638216.  
 635512. 632737. 629896. 626995. 624038. 621028. 617971. 614870. 611730. 608553.  
 605343. 602103. 598837. 595547. 592237. 588908. 585565. 582208. 578840. 575464.  
 572082. 568698. 565302. 561905. 558507. 555109. 551712. 548318. 544928. 541543.  
 538165. 534796. 531435. 528085. 524746. 521419. 518105. 514805. 511519. 508250.  
 504996. 501759. 498540. 495339. 492156. 488993. 485849. 482718. 479594. 476477.

382.9 382.8 382.7 382.6 382.5 382.4 382.3 382.2 382.1 382.0  
 382.2 382.1 382.0 381.9 381.8 381.7 381.6 381.5 381.4 381.3  
 382.6 382.5 382.4 382.3 382.2 382.1 382.0 381.9 381.8 381.7  
 387.0 387.1 387.2 387.3 387.4 387.5 387.6 387.7 387.8 387.9  
 387.1 387.0 386.9 386.8 386.7 386.6 386.5 386.4 386.3 386.2  
 386.5 386.4 386.3 386.2 386.1 386.0 385.9 385.8 385.7 385.6  
 385.8 385.7 385.6 385.5 385.4 385.3 385.2 385.1 385.0 384.9  
 385.0 384.9 384.8 384.7 384.6 384.5 384.4 384.3 384.2 384.1  
 384.2 384.1 384.0 383.9 383.8 383.7 383.6 383.5 383.4 383.3  
 383.4 383.3 383.2 383.1 383.0 382.9 382.8 382.7 382.6 382.5

PEAK OUTFLOW IS 34422. AT TIME 70.00 HOURS

PEAK 34422. 975.  
 CFS 34422. 975.  
 CMS 975.  
 INCHES 0.39 1.54 4.42 9.99  
 MM 9.88 39.23 112.30 253.63  
 AC-FT 17050. 67753. 193970. 438069.  
 THOUS CU H 21043. 83572. 239259. 540350.

STATION DAM, PLAN 1, RATIO 3  
END-OF-PERIOD HYDROGRAPH ORDINATES

21236. 19948. 20957. 39161. 39493. 35768. 32893. 30207. 27447. 24924.  
 21084. 19832. 22480. 39971. 39153. 35401. 32634. 30207. 27447. 24924.  
 20933. 19726. 24426. 40442. 38800. 35401. 32634. 30207. 27447. 24924.  
 20785. 19631. 26642. 40679. 38435. 34713. 32107. 29379. 26676. 24190.  
 20639. 19538. 29035. 40773. 38062. 34412. 31840. 29103. 26423. 23948.  
 20496. 19455. 31237. 40744. 37681. 34162. 31571. 28826. 26171. 23707.  
 20361. 19400. 33072. 40613. 37297. 33908. 31301. 28550. 25920. 23467.  
 20253. 19376. 34603. 40395. 36911. 33654. 31029. 28273. 25669. 23229.  
 20165. 19487. 36397. 40120. 36526. 33404. 30756. 27997. 25420. 22993.  
 20064. 20003. 37968. 39816. 36144. 33150. 30482. 27722. 25172. 22758.  
 482507. 453248. 476184. 699662. 701691. 676571. 609100. 572456.  
 479052. 450625. 501594. 699662. 701691. 676571. 609100. 572456.  
 475633. 448213. 529402. 697332. 697332. 670652. 637837. 605442.  
 472261. 446338. 561373. 708712. 695125. 667608. 637837. 605442.  
 468956. 443933. 593534. 709255. 692723. 664508. 630780. 594435.  
 465697. 442046. 622770. 709091. 690221. 661350. 627212. 590763.  
 462635. 440796. 647145. 708327. 687645. 658134. 623622. 587092.  
 460181. 440263. 666537. 707058. 689882. 654864. 620014. 583424.  
 45891. 442765. 681309. 705441. 682246. 651544. 616389. 579762.  
 454500. 692116. 703636. 679441. 648178. 612750. 576105. 540060.  
 455891. 450176. 442765. 681309. 705441. 682246. 651544. 616389. 579762. 543609.

536527. 533011. 529512. 526031. 522568. 519126. 515703. 512301. 508920. 505560.

STAGE



PEAK OUTFLOW IS 40773. AT TIME 70.00 HOURS

STATION DAN, PLAN 1, RATIO 4  
END-OF-PERIOD HYDROGRAPH ORDINATES

STORAGE							
482520.	475686.	472346.	465091.	462962.	460891.	459451.	457601.
455228.	450813.	449080.	447436.	446094.	445225.	451152.	469202.
501452.	579025.	626181.	673600.	716087.	770107.	798115.	812169.
821403.	826777.	829054.	828664.	826927.	824409.	817680.	813928.
810064.	806103.	797936.	793753.	789517.	780921.	776576.	772210.
767028.	759038.	754640.	750245.	745858.	741480.	737114.	728421.
724097.	719791.	715504.	708990.	702764.	698558.	690209.	686064.
681936.	673729.	669643.	665563.	661480.	653289.	649182.	645070.
640956.	636841.	632728.	628619.	624514.	620417.	612251.	608184.
600092.	596070.	588075.	584106.	576229.	572322.	568430.	564573.

STAGE											
382.9	382.8	382.7	382.6	382.5	382.4	382.3	382.2	382.1	382.0	382.5	382.4
382.3	382.2	382.1	382.0	381.9	381.8	381.7	381.6	381.5	381.4	381.3	381.2
383.4	383.3	383.2	383.1	383.0	382.9	382.8	382.7	382.6	382.5	382.4	382.3
390.9	391.0	391.1	391.2	391.3	391.4	391.5	391.6	391.7	391.8	391.9	392.0
390.6	390.5	390.4	390.3	390.2	390.1	390.0	389.9	389.8	389.7	389.6	389.5
389.5	389.4	389.3	389.2	389.1	389.0	388.9	388.8	388.7	388.6	388.5	388.4
388.6	388.5	388.4	388.3	388.2	388.1	388.0	387.9	387.8	387.7	387.6	387.5

387.6  
386.7  
385.7

387.5  
386.6  
385.6

387.4  
386.5  
385.5

387.3  
386.4  
385.4

387.  
386.3  
385.3

387.1  
386.2  
385.2

387.0  
386.1  
385.1

386.9  
386.0  
385.0

386.8  
385.9  
384.9

386.7  
385.8  
384.9

PEAK OUTFLOW IS 67761. AT TIME 68.00 HOURS

CFS	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CMS	67761.	67574.	65696.	56676.	3860013.
INCHES	1919.	1913.	1860.	1605.	109304.
MM		0.76	2.97	7.69	14.54
AC-FT		19.40	75.44	195.26	369.40
THOUS CU M		33508.	130305.	337247.	638019.
		41331.	160730.	415989.	786985.

.....

.....

.....

.....

.....

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS  
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)  
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS			
				RATIO 1 0.50	RATIO 2 0.60	RATIO 3 0.70	RATIO 4 1.00
HYDROGRAPH AT	1	66.00 ( 170.94)	1	59755. ( 1692.08)	71706. ( 2030.50)	83657. ( 2368.91)	119510. ( 3384.16)
	2	303.00 ( 784.77)	1	56961. ( 1612.97)	68354. ( 1935.56)	79746. ( 2258.16)	113923. ( 3225.94)
HYDROGRAPH AT	3	454.00 ( 1175.86)	1	109391. ( 3097.61)	131269. ( 3717.13)	153147. ( 4336.65)	218782. ( 6195.21)
	3 COMBINED	823.00 ( 2131.57)	1	163181. ( 4620.79)	195818. ( 5544.95)	228454. ( 6469.10)	326363. ( 9241.58)
ROUTED TO	DAM	823.00 ( 2131.57)	1	30852. ( 873.62)	34422. ( 974.73)	40773. ( 1154.56)	67761. ( 1918.77)

## SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1 .....

RATIO OF P/F	MAXIMUM RESERVOIR W.S.-ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
0.50	386.10	0.0	617657.	30852.	0.0	70.00	0.0
0.60	387.21	0.01	664620.	34422.	4.00	70.00	0.0
0.70	388.26	1.06	709255.	40773.	56.00	70.00	0.0
1.00	391.09	3.89	829454.	67761.	102.00	68.00	0.0

ELEVATION  
STORAGE  
OUTFLOWINITIAL VALUE  
383.00  
486000.  
21389.SPILLWAY CREST  
371.50  
0.  
0.TOP OF DAM  
387.20  
664260.  
34392.

APPENDIX D

REFERENCES

### GENERAL

Martin, R.J., 1974, Flood Plain Management Study, prepared for Tompkins County Department of Planning, Ithaca, New York.

New York State Museum and Science Service, 1961, Geologic Map of New York, Finger Lakes Sheet.

University of the State of New York, reprinted 1973, Geology of New York, Education Leaflet 20.

Von Engeln, O.D., 1969, The Finger Lakes Region: Its Origin and Nature, Cornell University Press

### HYDRAULICS

Chow, Ven Te, 1959, Open Channel Hydraulics, McGraw Hill.

King, H.W. and E.F. Brater, 1963, Handbook of Hydraulics, 5th Edition, McGraw-Hill

#### U.S. Army Corps of Engineers:

HEC-1 Flood Hydrograph Package - Dam Safety Version, September 1978.

Engineering Manual 1110-2-1405; Flood-Hydrograph Analyses and Computations, August 1959.

#### U.S. Department of Agriculture, Soil Conservation Service:

National Engineering Handbook; Section 4 - Hydrology, August 1972.

#### U.S. Department of Commerce; Weather Bureau:

Hydrometeorological Report No. 33: Seasonal Variation of the Probable Maximum Precipitation East of the 105th Meridian for Areas from 10 to 1,000 Square Miles and Durations of 6,12,24, and 48 Hours, April 1956.

#### U.S. Department of the Interior:

BUREC, 1977, Design of Small Dams, 2nd Ed. (rev. reprint).

USGS, 1980, Water Resources Data For New York, Western New York, USGS Water Data Report NY-80-3.

APPENDIX E

PREVIOUS INSPECTION REPORTS  
AND AVAILABLE DOCUMENTS



DAM INSPECTION REPORT  
(By Visual Inspection)

Dam Number	River Basin	Town	County	Hazard Class	Date & Inspector
369	Oswego	Munehius	Cayuga	C	9/9/76 KJ

Type of Construction

- ☐ Earth w/concrete spillway  
☐ Earth w/drop inlet pipe  
☐ Earth w/stone or riprap spillway  
☒ Concrete  
☐ Stone  
☐ Timber

Use

- ☐ Water Supply  
☒ ~~Reser~~ D.O.T. Lock  
☐ Recreation  
☐ Fish and Wildlife  
☐ Farm Pond  
☐ No Apparent Use-Abandoned

Estimated Impoundment Size

- ☐ 1-5 acres  
☐ 5-10 acres  
☒ Over 10 acres

Estimated Height of Dam above Streambed

- ☐ Under 10 feet  
☒ 10-25 feet  
☐ Over 25 feet

CAPACITY  $\cdot 12 \times 66.27 \times 640 = 171,187$  A.F.

Condition of Spillway

SAY 172,000 A.F. (G)

- ☒ Service satisfactory  
☐ In need of repair or maintenance  
☒ Auxiliary satisfactory  
☐ In need of repair or maintenance

Explain: \_\_\_\_\_

Condition of Non-Overflow Section

- ☒ Satisfactory  
☐ In need of repair or maintenance
- Explain: \_\_\_\_\_

Condition of Mechanical Equipment

- ☒ Satisfactory  
☐ In need of repair or maintenance
- Explain: \_\_\_\_\_

Evaluation (From Visual Inspection)

- ☒ No defects observed beyond normal maintenance  
☐ Repairs required beyond normal maintenance

8-64-369 Oswego

Form W51. 5-12-16-2000 (16-16756)

Acc. 385

(NOTICE: After filling out one of these forms as completely as possible for each dam in your district, return it at once to the Conservation Commission, Albany.)

STATE OF NEW YORK  
CONSERVATION COMMISSION  
ALBANY

DAM REPORT

July  
Aug 3 1, 1918  
(Date)

CONSERVATION COMMISSION,

DIVISION OF WATERS.

GENTLEMEN:

I have the honor to make the following report in relation to the structure known as the Mud Lock Lock I C & S Dam.

This dam is situated upon the Schenectady River  
(Give name of stream)  
in the Town of Circleville, Cayuga County,  
about 2 mile from the Village or City of Cayuga  
(State distance)  
The distance down stream from the dam, to the Free Bridge  
(Up or down) (Give name of nearest important stream or of a bridge)  
is about 1 mile  
(State distance)

The dam is now owned by State of N.Y.  
(Give name and address in full)  
and was built in or about the year 1880, and was extensively repaired or reconstructed during the year 1880.

As it now stands, the spillway portion of this dam is built of Concrete & masonry  
(State whether of masonry, concrete or timber)  
and the other portions are built of timber  
(State whether of masonry, concrete, earth or timber with or without rock fill)

As nearly as I can learn, the character of the foundation bed under the spillway portion of the dam is glacial drift, and under the remaining portions such foundation bed is glacial drift.

The total length of this dam is.....feet. The spillway or waste-weir portion, is about.....feet long, and the crest of the spillway is about.....feet below the abutment.

The number, size and location of discharge pipes, waste pipes or gates which may be used for drawing off the water from behind the dam, are as follows:.....

At the time of this inspection the water level above the dam was.....ft.....in.  
below the crest of the spillway.  
above

(State briefly, in the space below, whether, in your judgment, this dam is in good condition, or bad condition, describing particularly any leaks or cracks or erosions which you may have observed.)

*This is a state Dam and in fine condition*

Reported by *Royce Johnson*  
(Signature)

*8. Rushville*  
.....  
(Address—Street and number, P. O. Box or R. F. D. route)

*N.Y.*  
.....  
(Name of place)

December 3, 1915.

Hon. Frank M. Williams,  
State Engineer,  
Albany, N. Y.

Dear Sir:-

Receipt is acknowledged of your letter of November 29, 1915, enclosing sketch for the proposed fishway for dam #1 Cayuga-Seneca Canal.

We prefer a fishway with a slope of about one vertical to four horizontal and a width of four feet with compartments six feet long, the partitions to run obliquely; the top partition to have an opening 18 inches square and the bottom partition an opening 12 inches square and proportional in between.

We enclose herewith a pamphlet on Fishways for Dam, which we hope will be of use to you in this work.

Very truly yours,

GEO. D. PRATT, Commissioner,

By

Division Engineer.

McK/C.

Encl.

## INSPECTION GUIDELINES

FOR

### 3C.000 TAINTOR GATES AND TAINTOR DAMS

The following guidelines are related to the Structure Condition Report for Taintor Gates and Dams (CAN 95) by the numbering system for the various elements.

The inspector should refer to Forms Instruction 900 CAN 95 before filling out the condition report.

#### 3C.100 Stream Channel

##### .101 Adequacy of Openings

Adequacy may be determined by checking upstream high water level recordings during past years.

##### .102 Freedom from Erosion & Scour

Upstream and downstream should be scrutinized for any indication of deepening or widening of the lateral dimension of flow area. Check the graph of any bottom profile available from Regional surveys.

##### .103 Freedom from Obstructions

Debris or vegetation in the Waterways both upstream and downstream may reduce the width of the waterway, contributing to scour. Sand and gravel bars formed in the channel may increase stream velocity and lead to scour.

##### .104 Bank Protection

Examine the condition and adequacy of existing bank protection. Note whether channel changes are impairing or decreasing the effectiveness of present protection.

#### 3C.200 Substructure

##### .201 Sills & Aprons

##### .202 Piers Between Gates

##### .203 Abutments

##### .204 Wing Walls

These elements containing concrete are susceptible to scaling, cracking, spalling, movement and rotation. Any of these conditions should be noted. Evidence of movement may be observed by noting any scoring of concrete by sides of gates or excessive wear on gate seal; and also by noting any displacement at joints in the concrete.

### 3C.300 Superstructure

- .301 Gate Skinplate
- .302 Side Seal Strips
- .303 Bottom Seal Strips
- .304 Main Structural Members
- .305 Cross Bracing
- .309 Railings

All steel elements should be inspected for rust, erosion, cracks, buckles, kinks, fine cracks at stress connections, steel incased in concrete for deterioration or movement at their common exposure and all rivets and bolts for tightness. Seal strips may have become worn to the degree that they no longer seal properly and need replacement.

#### .306 Counterweights

Determine if the counterweights are sound and properly affixed. Where steel members pass through or are embedded in the concrete check for corrosion of the steel member or rust stains on the concrete. Look for cracks and spalls. Determine if the gates are in balance.

#### .307 Bearings & Pins

Examine all bearings and pins for weakness, excessive play, corrosion, and undesirable deflection or bending.

#### .308 Needle Beam Catwalk

Statement .301 thru .305 referring to steel elements shall apply here. All wooden walkways should be inspected for signs of decay, weathering, and wear. The needlebeam should be positioned so that the operator's gears properly mesh with the rack.

#### .310 Paint

Examine all paint for cracking or chipping, scaling, rust, pimples, and chalking. If paint film has disintegrated, note if the prime coat or surface of metal is exposed. Note if spot or extensive painting is needed. Look for paint failure on horizontal surfaces or those which are most exposed to sunlight or moisture. Give particular attention to areas around rivets and bolts, the ends of beams, the seams of built-up members, the unwelded ends of stiffeners, and any other areas difficult to paint or that retain moisture.

### 3C.400 Machinery (Electrical)

#### .401 Motors

Determine if there is ample wear length on brushes, ventilating openings are unobstructed and any abnormal vibration. The commutator or slip rings should be clean. The motor should be properly lubricated and kept dry.

.402 Gears

The gears are to be properly lubricated, tight on shafts, no broken or cracked teeth, properly meshed and aligned, with no excessive wear.

.403 Bearings

Bearings shall be free of excessive play and properly lubricated.

.404 Wiring

Inspect any exposed wiring for signs of faulty, worn or damaged insulation. Also look for loose wires, poor wire splices, and inadequate securing of ground lines. Check inside of junction boxes for excessive moisture, drain hole, poor wire splices, and loose connections. Covers for junction outlets and switch boxes should be in place. Determine insulation resistance value.

.405 Starters, Switches

Check contacts of motor starters, limit switches and overtravel switches for pitting. Mechanical linkage should be clean, dry, and lubricated. Contactor coils are to be clean and leads secure.

.406 Overload Protection

Determine if the circuits contain the proper amperage circuit breakers and/or fuses.

3C.500 Operators

.501 Hand Wheel Bearings

The bearings should be lubricated, and aligned so that the gears mesh properly. Any excessive wear should be noted.

.502 Hand Wheel Gears

Gears should be checked for tightness and lubrication. Cracked or broken teeth shall be noted.

.503 Housing

The housing assemblies should be free of any cracks or broken areas.

.504 Fasteners

Operator housing assemblies shall be firmly and securely anchored in place. Check for loose or missing nuts, bolts, rivets, etc.

.505 Gear Covers

Gear Covers should be in a position that will protect the gears from weather and to prevent the operator from entanglement while the machinery is in operation.

- .506 Locking Devices  
Locking Devices should be provided to prevent unauthorized use.

3C.600 Machinery (Lifting)

- .601 Pinion Shaft  
The pinion shaft should be straight and true. The shaft should also be examined for excessive wear and proper lubrication at the bearings. Inspect for excessive twisting of the shaft.
- .602 Bearings  
The pinion shaft bearings shall be free of excessive wear and properly lubricated.
- .603 Gears  
Check the alignment of all gears, locks, and interlocking devices. There should be adequate lubrication of all movable parts, particularly where meshing or contact occurs. All gears will be inspected for cracked teeth or hub. Keys are to fit tightly in keyways, holding gears firmly on shafts.
- .604 Cable Drums  
Note if drums are tight on shaft and if the cables are properly aligned on drums. Excessive wear of drum grooves should be noted.
- .605 Rack Segments  
Inspect rack segments for excessive wear, broken or missing teeth, proper lubrication and alignment for mesh with the pinion gear.
- .606 Lifting Cables  
Lifting cables should be inspected for wear damage, corrosion and inadequate lubrication. Cable connectors must be secure.
- .607 Couplings  
Couplings shall be tight on shafts with all flange bolts in place and tight.

3C.700 Gate Bearing Points

Examine all bearings and pins for weakness, excessive play, corrosion, and undesirable deflection or bending.



FORMS INSTRUCTION

Subj: Condition Report for  
Taintor Gates and Taintor Dams

PURPOSE

For recording the results of field inspections of all taintor gates and taintor dams maintained by the Waterways Maintenance Subdivision. This form is also the source of input to the EDP program for listing the condition information.

PREPARATION

Completed in the field, in black ball point or black felt tipped pen, by the person performing the inspection. One form is used for each structure to be inspected.

1. The field inspector fills out the heading and enters the year and month when the inspection was performed in the boxes provided. Enter single digit months in the rightmost box.
2. Boxes 1 thru 7 - Structure Identification Number. The field inspector enters the number for the taintor gate or taintor dam being inspected. The number is obtained from the EDP Listing of the Structure Inventory.
3. Boxes 8 thru 49 inclusive (except for boxes 28 and 29). The rating numbers to be inserted in these boxes by the field inspector are as follows:

- 9 - Excellent
- 7 - Good
- 5 - Fair
- 3 - Poor
- 1 - Poor minus

Criteria for applying these ratings to the various elements of the structure may be found in section 3C.000 of the Maintenance Quality Manual.

NOTE: There must be an entry in every box.

- a. If there is no such element on the structure - enter N
  - b. If the element is submerged or otherwise inaccessible - enter X
4. Where the item to be rated covers more than one element on both the left and right (for example - bank protection, piers between gates); enter an overall rating in the proper box and indicate any particularly bad conditions in the adjacent comments section.

PREPARATION - Cont'd.

5. If the designation left or right is used under Comments, it must be in reference to the structure when facing downstream.
6. Box 50. The Regional Waterways Engineer only, enters one of the following rating numbers in this box:
  - 9 - Good condition - no repairs necessary.
  - 7 - Preventive maintenance or minor repairs needed.
  - 5 - Major repairs needed - deferred scheduling.
  - 3 - Major repairs needed - schedule within one year.
  - 1 - Immediate attention needed - schedule as soon as possible.
7. The Regional Waterways Engineer will sign the completed form where indicated opposite box 50.

DISPOSITION

1. The Regional Waterways Engineer will have two copies made of the original report. He will then forward the original and one copy to the Waterways Maintenance Subdivision - Main Office. The other copy will be retained in the Regional Waterways Office files.
2. The Waterways Maintenance Subdivision - Main Office will review the form for completeness and reasonableness of entries. The original will be kept in that office and the copy will be forwarded to the Bureau of Data Services for processing into the data file.

RELATED FORMS

None

AD-A109 968

METCALF AND EDDY OF NEW YORK INC NY  
NATIONAL DAM SAFETY PROGRAM. MUD LOCK C&S CANAL DAM (INVENTORY --ETC(U)  
SEP 81 G P FULTON

F/G 13/13


DACW51-81-C-0044

NL

UNCLASSIFIED

2 - 2

2 - 1 (for rep)




END

DATE

FILMED

3 82

DTIC



MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A

CAN 95 (4/72)

DEPARTMENT OF TRANSPORTATION  
WATERWAYS MAINTENANCE SUBDIVISION  
**TAINTOR GATES & DAMS**

[23] YEAR [08] MONTH

CONDITION REPORT

INSPECTED BY B. AldrichHISTORIC NAME Movable Dam-Taintor Type - lock 1 TITLE ACE

STRUCTURE IDENTIFICATION NO

W 

6	3	0	0	1	3	6
1	2	5	6	7		

3C.100 STREAM CHANNEL

COMMENTS

.101 ADEQUACY OF OPENINGS

[7]

.102 FREEDOM FROM EROSION &  
SCOUR

[7]

.103 FREEDOM FROM OBSTRUCTIONS

[7]

.104 BANK PROTECTION

[7]

3C.200 SUBSTRUCTURE

.201 SILLS &amp; APRONS

[X]

substantial leakage

.202 PIERS BETWEEN GATES

[7]

some scaling

.203 ABUTMENTS

[7]

.204 WING WALLS

[5]

3C.300 SUPERSTRUCTURE

.301 GATE SKINPLATE

[X]

Fair - some need replacement

.302 SIDE SEAL STRIPS

[5]

All leak

.303 BOTTOM SEAL STRIPS

[X]

substantial leakage

.304 MAIN STRUCTURAL MEMBERS

[7]

.305 CROSS BRACING

[5]

.306 COUNTERWEIGHTS

[7]

.307 BEARINGS &amp; PINS

[7]

.308 NEEDLE BEAM CATWALK

[7]

Remove sand from under wood walk

.309 RAILINGS

[7]

.310 PAINT

[5]

(OVER)

YEAR LAST PAINTED

[7]

# 3C.400 MACHINERY, ELECTRICAL

- .401 MOTORS
- .402 GEARS
- .403 BEARINGS
- .404 WIRING
- .405 STARTERS, SWITCHES
- .406 OVERLOAD PROTECTION

N  
30  
N  
31  
N  
32  
N  
33  
N  
34  
N  
35

## COMMENTS

# 3C.500 OPERATORS

- .501 HAND WHEEL BEARINGS
- .502 HAND WHEEL GEARS
- .503 HOUSING
- .504 FASTENERS
- .505 GEAR COVERS
- .506 LOCKING DEVICES

7  
36  
7  
37  
7  
38  
7  
39  
7  
40  
7  
41

# 3C.600 MACHINERY, LIFTING

- .601 PINION SHAFT
- .602 BEARINGS
- .603 GEARS
- .604 CABLE DRUMS
- .605 RACK SEGMENTS
- .606 LIFTING CABLES
- .607 COUPLINGS

7  
42  
7  
43  
7  
44  
N  
45  
7  
46  
N  
47  
7  
48  
7  
49

# 3C.700 GATE PIVOT BEARING POINTS

## GENERAL RECOMMENDATION

## OVERALL COMMENT

7  
50

*M.D. Hewitson*  
REGIONAL WATERWAYS ENGINEER

DEPARTMENT OF TRANSPORTATION  
WATERWAYS MAINTENANCE SUBDIVISION  
**TAINTOR GATES & DAMS**

**79** YEAR ☐ MONTH

CONDITION REPORT

INSPECTED BY B. Aldrich

HISTORIC NAME Movable Dam - Taintor Type - Lock 1 TITLE ACE

STRUCTURE IDENTIFICATION NO

W **6** **2001** **SC**

3C.100 STREAM CHANNEL

COMMENTS

.101 ADEQUACY OF OPENINGS

**7**

.102 FREEDOM FROM EROSION &  
SCOUR

**7**

.103 FREEDOM FROM OBSTRUCTIONS

**7**

.104 BANK PROTECTION

**7**

3C.200 SUBSTRUCTURE

.201 SILLS & APRONS

**X**

.202 PIERS BETWEEN GATES

**3**

.203 ABUTMENTS

**7 7**

.204 WING WALLS

**5 7**

3C.300 SUPERSTRUCTURE

.301 GATE SKINPLATE

**X**

.302 SIDE SEAL STRIPS

**3**

.303 BOTTOM SEAL STRIPS

**X**

.304 MAIN STRUCTURAL MEMBERS

**7**

.305 CROSS BRACING

**4**

.306 COUNTERWEIGHTS

**7**

.307 BEARINGS & PINS

**7**

.308 NEEDLE BEAM CATWALK

**7**

.309 RAILINGS

**6**

.310 PAINT

**9**

(OVER)

YEAR LAST PAINTED

**7**

**1**

CAN 95 REVERSE

### 3C.400 MACHINERY, ELECTRICAL

.401 MOTORS

.402 GEARS

.403 BEARINGS

.404 WIRING

.405 STARTERS, SWITCHES

.406 OVERLOAD PROTECTION

### 3C.500 OPERATORS

.501 HAND WHEEL BEARINGS

.502 HAND WHEEL GEARS

.503 HOUSING

.504 FASTENERS

.505 GEAR COVERS

.506 LOCKING DEVICES

### 3C.600 MACHINERY, LIFTING

.601 PINION SHAFT

.602 BEARINGS

.603 GEARS

.604 CABLE DRUMS

.605 RACK SEGMENTS

.606 LIFTING CABLES

.607 COUPLINGS

### 3C.700 GATE PIVOT BEARING POINTS

GENERAL RECOMMENDATION

OVERALL COMMENT

## COMMENTS

N

30

N

31

N

32

N

33

N

34

N

35

7

36

7

37

7

38

7

39

7

40

7

41

7

42

3

43

5

44

N

45

5

46

N

47

7

48

5

49

4

50

*L. Burns*  
REGIONAL WATERWAYS ENGINEER



DEPARTMENT OF TRANSPORTATION  
WATERWAYS MAINTENANCE SUBDIVISION

## TAINTOR GATES &amp; DAMS

☒ YEAR ☐ MONTH

CONDITION REPORT

INSPECTED BY E. AldrichHISTORIC NAME Movable Dam-Taintor Type - Lock TITLE ACESTRUCTURE IDENTIFICATION NO W 6 0001 3C

## 3C.100 STREAM CHANNEL

## COMMENTS

- .101 ADEQUACY OF OPENINGS
- .102 FREEDOM FROM EROSION & SCOUR
- .103 FREEDOM FROM OBSTRUCTIONS
- .104 BANK PROTECTION

## 3C.200 SUBSTRUCTURE

- .201 SILLS & APRONS
- .202 PIERS BETWEEN GATES
- .203 ABUTMENTS
- .204 WING WALLS

## 3C.300 SUPERSTRUCTURE

- .301 GATE SKINPLATE
- .302 SIDE SEAL STRIPS
- .303 BOTTOM SEAL STRIPS
- .304 MAIN STRUCTURAL MEMBERS
- .305 CROSS BRACING
- .306 COUNTERWEIGHTS
- .307 BEARINGS & PINS
- .308 NEEDLE BEAM CATWALK
- .309 RAILINGS
- .310 PAINT

(OVER) YEAR LAST PAINTED

-65-

CAN 95 REVERSE

3C.400 MACHINERY, ELECTRICAL

COMMENTS

.401 MOTORS

N  
30

.402 GEARS

N  
31

.403 BEARINGS

N  
32

.404 WIRING

N  
33

.405 STARTERS, SWITCHES

N  
34

.406 OVERLOAD PROTECTION

N  
35

3C.500 OPERATORS

.501 HAND WHEEL BEARINGS

7  
36

.502 HAND WHEEL GEARS

7  
37

.503 HOUSING

7  
38

.504 FASTENERS

7  
39

.505 GEAR COVERS

7  
40

.506 LOCKING DEVICES

7  
41

3C.600 MACHINERY, LIFTING

.601 PINION SHAFT

7  
42

.602 BEARINGS

3  
43

.603 GEARS

5  
44

.604 CABLE DRUMS

N  
45

.605 RACK SEGMENTS

5  
46

.606 LIFTING CABLES

N  
47

.607 COUPLINGS

7  
48

3C.700 GATE PIVOT BEARING  
POINTS

5  
49

GENERAL RECOMMENDATION

4  
50

*L. Burns*  
REGIONAL WATERWAYS ENGINEER

OVERALL COMMENT

DEPARTMENT OF TRANSPORTATION  
 WATERWAYS MAINTENANCE SUBDIVISION

**TAINTOR GATES & DAMS**

75 YEAR 5 MONTH

CONDITION REPORT

 INSPECTED BY R. Aldrich

 HISTORIC NAME Movable Dam - Taintor Type - Lock 1 TITLE ACE

STRUCTURE IDENTIFICATION NO

 W 6 3 0 0 1 3 C  
1 2 3 4 5 6 7

## 3C.100 STREAM CHANNEL

## COMMENTS

.101 ADEQUACY OF OPENINGS

 7  
8

 .102 FREEDOM FROM EROSION &  
SCOUR

 7  
9

.103 FREEDOM FROM OBSTRUCTIONS

 7  
10

.104 BANK PROTECTION

 7  
11

## 3C.200 SUBSTRUCTURE

.201 SILLS &amp; APRONS

 7  
12

.202 PIERS BETWEEN GATES

 7  
13

some scaling

.203 ABUTMENTS

 7 7  
14 15

.204 WING WALLS

 5 7  
16 17

## 3C.300 SUPERSTRUCTURE

.301 GATE SKINPLATE

 X  
18

.302 SIDE SEAL STRIPS

 5  
19

all leak

.303 BOTTOM SEAL STRIPS

 X  
20

.304 MAIN STRUCTURAL MEMBERS

 7  
21

.305 CROSS BRACING

 5  
22

.306 COUNTERWEIGHTS

 7  
23

.307 BEARINGS &amp; PINS

 7  
24

.308 NEEDLE BEAM CATWALK

 7  
25

remove sand from  
beneath walk

.309 RAILINGS

 7  
26

.310 PAINT

 5  
27

(OVER)

YEAR LAST PAINTED

 7 1  
28 29

## 3C.400 MACHINERY, ELECTRICAL

## COMMENTS

.401 MOTORS

N  
30

.402 GEARS

N  
31

.403 BEARINGS

N  
32

.404 WIRING

N  
33

.405 STARTERS, SWITCHES

N  
34

.406 OVERLOAD PROTECTION

N  
35

## 3C.500 OPERATORS

.501 HAND WHEEL BEARINGS

7  
36

.502 HAND WHEEL GEARS

7  
37

.503 HOUSING

7  
38

.504 FASTENERS

7  
39

.505 GEAR COVERS

7  
40

.506 LOCKING DEVICES

7  
41

## 3C.600 MACHINERY, LIFTING

.601 PINION SHAFT

7  
42

.602 BEARINGS

7  
43

.603 GEARS

7  
44

.604 CABLE DRUMS

N  
45

.605 RACK SEGMENTS

7  
46

.606 LIFTING CABLES

N  
47

.607 COUPLINGS

7  
483C.700 GATE PIVOT BEARING  
POINTS7  
49

## GENERAL RECOMMENDATION


5  
50L. Burns  
REGIONAL WATERWAYS ENGINEER

## OVERALL COMMENT


Generally good but seals should be replaced.

APPENDIX F

DRAWINGS



VICINITY MAP  
MUD LOCK C&S CANAL DAM  
I.D. NO. NY 416




TOPOGRAPHIC MAP  
MUD LOCK C&S CANAL DAM  
I.D. NO. NY 416







12








4





# Contract A

BYUG (AND)

For the con

DETAIL LOCATION  
 LOCK NO 1 & 2 AMN  
 STA 5687.00 TO STA 5722.6

S. 10 10

James Fournier


14

24 11 1961

+

6


L A K E O N T A R I O













MADE BY WILLIAMSON  
CHECKED BY WILLIAMSON





**LEGEND**  
 PRECIPITATION STATION  
 FLOW COURSE  
 EXCHANGE STATION  
 RATE CONTROL WORKS  
 CANALS  
 FEEDERS



STATE OF NEW YORK  
 DEPARTMENT OF TRANSPORTATION  
 MAP OF  
**OSWEGO RIVER WATER SHED**



FEBRUARY 27, 1945

SQUARE MILES		1941/42
100	120	
87	1.8	
757	14.8	
44	1.3	
1572	26.8	
806	12.3	
2048	37.6	
1074	23.7	
88	1.5	
1073	27.3	
1090	10.0	


6



ELEVATION

-NOTES-

Produce to make and select, put in front of a well  
longitudinal produce, which to be left for some  
time, then to be used, the same of a well  
Duck! better, if you want to try, is a well  
Duck of a well, to be used, and to be used  
the days to be filled with, then, as per  
Crib to be built, and to be used, as per




LOCUST HILL PLANT  
100-100-0

**-NOTES-**

- Free ends of wire are attached to the bottom of the test  
Longitudinal members are to be left free to expand & contract  
Transverse members which extend from ends to ends of ends.  
Don't bother if any part of the wire is not in the test  
Ends of ends to be fastened at each longitudinal member with for 1/2 in. x 1/2 in. steel  
All holes to be filled with epoxy, as per specifications  
Ends to be built continuous or as separate ends as determined by the Engineer






Examined and certified  
*[Signature]* 1914  
 Recording Engineer


SECTION B-B  
TOP REMOVED








PLAN OF ABUTMENT




FRONT ELEVATION


2




PLAN OF PIER  
Scale 1/4" = 1'-0"




ELEVATION




FOUNDATION PLAN  
Scale 1/4" = 1'-0"






Section of pier showing  
the location of the  
foundations and the  
piles.



Section of pier showing  
the location of the  
foundations and the  
piles.








DRAWN BY [Signature]  
 CHECKED BY [Signature]  
 IN CHARGE BY [Signature]


FOUNDATION PLAN  
 SCALE 1/4" = 1'-0"



[illegible]

SECTION OF SILL

**NOTES**


[illegible]

# the construction PLAN


### Exercises and Assignments



DETAIL SHOWING LOCATION OF ANCHOR BOLTS  
Scale 1" = 1'-0"




DETAIL OF ANCHOR BOLTS  
Scale 1" = 1'-0"



DETAIL OF NOTCHED PILE UNDER SILL  
Scale 1" = 1'-0"



DETAIL OF CUSTOM BLOCK & ANCHORS  
Scale 1" = 1'-0"



DETAIL OF SHEET PILING  
Scale 1" = 1'-0"

# Contract

DAYUGA AND SENECA CANAL


For the construction of Lock No. 1 and Dam No. 1 near Cayuga.

## PLAN & DETAILS OF DAM NO. 1

Scales as indicated.

Engineered and approved


*[Signature]*  
Civil Engineer



Notes:  
 The figure ABCD is a parallelogram  
 The lines CE and BE are parallel  
 E is the center of gravity of the  
 moving parts at all positions of  
 the gate


After gate is erected and set  
 (by trial) with concrete blocks  
 in both directions. Concrete  
 must be placed symmetrically  
 and open for drainage

Wooden needles not  
 included in this contract



After  
 counter  
 center  
 size of  
 and of  
 of the

Sectional Elevation






2

and counterweight is in place fill this slot with blocks until the gate works with equal ease. Concrete blocks must be finally grouted in place and leveled from center toward ends leaving ends of

1-12 L 25# } Countersink rivets in this flange  
2-L 25# 3/8 }

Scale for 1/4" = 1'-0"  
1/4" = 1'-0"  
1/4" = 1'-0"

C.G. of Counterweight  
Balance beam, and Link



Drilled to suit casting

1-12 L 25# }  
2-L 25# 3/8 }

30'-0" between walls

This end  
Other end  
Drilled to suit casting

30'-0" on the side of only

End Beam

30'-0" Overall


### Detail of Needle Beam

Symmetrical about 2, except as shown and noted.

Scale 3/4" = 1'-0"

After shop drawings (except for counterweight) have been approved the Contractor shall determine the exact size and position of the counterweight and submit his figures for approval of the Engineer.

Symmetrical about 1 of counterweight



30'-0" Overall  
18'-0" Overall  
9'-0" Overall  
24'-0" Overall  
12'-0" Overall


Pack concrete thoroughly under B

30'-0" Overall

### Detail of Counterweight

Scale 3/4" = 1'-0"

6x45 Concrete



### Detail of Needle Beam.



symmetrical about  $z$ , except as shown and noted.

Scale 3 1/2"

Reinforcement  
10-1045 full in hand at 10:25 in 10:25  
B-10 10:10 - and 10:25 - 10:25  
12-10 10:10 - 10:25  
10:10 - 10:25




Weight




Made by A. J. ...  
 Traced by ...  
 1st Edition of A. J. ...  
 2nd Edition by ...

Plan  
 General Drawing of Timber Gate  
 Scale 1/4" = 1'-0"




After shop drawings except for counterweights have been approved the Contractor shall determine the exact size and position of the counterweight and submit his figures for approval of the Engineer.

32'-0" Overall  
**Detail of Needle Beam.**  
 Symmetrical about & except as shown and noted.  
 Scale 1/2" = 1'-0"



Reinforced  
 18-#10s (1/2")  
 8- " 18-#10  
 12- " 26-#10  
 2-#10s - 1/2"

12'-0"  
 33'-0" Overall  
**Detail of Counterweight.**  
 Scale 1/2" = 1'-0"  
 2nd Class Concrete.



**Sketch showing highest Position of Gate**  
 Scale 1/2" = 1'-0"

**Cont**  
 OAYUGA AND  
 For the construction of Lock  
**ASSEMBLY PLAN**  
 Scale

Examined and approved  
 4/10  
 Chief Engineer, Locks and Inspectors

5

30'-0" between walls

15'-0" side of only


Detail to suit existing

32'-0" Overall


### Detail of Needle Beam

Symmetrical about  $\bar{x}$  except as shown and noted.

Scale 3/16"



Reinforcement  
18 rods full length in each direction  
8" - 18 rods - and 32' - 10"  
12" - 26 rods - 5' - 3' 10"  
21 rods - 8' - 2" net area



Put concrete thorough under B



Overall  
underweight  
Concrete

## Contract A.

CAYUGA AND SENECA CANAL

For the construction of Lock No. 1 and Dam No. 1 near Cayuga

### ASSEMBLY PLAN OF TAINTOR GATE

Scales as indicated

Examined and approved

Examined and approved

*[Signature]*  
Chief Engineer and Inspector

*[Signature]*  
Chief Engineer and Inspector

